

Item Rate BoQ

Tender Inviting Authority: Commissioner, Thoothukudi City Municipal Corporation

Name of Work : Construction of Storm Water Drain at Krishna nagar main Road (138052R2358, Length = 556, Vent = 0.6), Perinba Nagar W/E (138052R2369, Length = 335, Vent = 0.6), Perinba Nagar N/S (138052R2368, Length = 180.5, Vent = 0.6), JS Nagar (138055R2410, Length = 286, Vent = 0.6), JS Nagar 4th Street (138055R2420, Length = 118, Vent = 0.6), Kumarasamy Nagar 3rd Street W/E (138056S1128, Length = 330, Vent = 0.9), Kumarasamy Nagar 2nd Street (138056S1148, Length = 143, Vent = 0.45), Pannai Nagar N/S (Kumarasamy Nagar 2nd Street to panai nagar end) (138056S1147, Length = 60.5, Vent = 0.45), Kumarasamy Nagar 2nd Street (138056S1129, Length = 350, Vent = 0.45), Pannai Nagar n/S to Kumarasamy Nagar 2nd Street (138056S1110, Length = 310, Vent = 0.45), Kumarasamy Nagar 4th Street North Side W/E (138056R2444, Length = 156, Vent = 0.45), Kumarasamy Nagar 4th Street South Side W/E (138056R2445, Length = 192, Vent = 0.45), Kumarasamy Nagar 3rd Street to 4th Street Link East Side N/S (138056R2446, Length = 35, Vent = 0.45), ThavasiPerumal Salai W/E (138056R2443, Length = 305, Vent = 0.45), Ambedkar Nagar Main Street N/S (138056S1139, Length = 175, Vent = 0.45), Thendral Street W/E (138056R2452, Length = 390, Vent = 0.45), Sakthi Nagar street (138057S1178, Length = 105, Vent = 0.45), SaweriyarPuram West 4th street W/E (Kovil Back Side) (138057S1191, Length = 550, Vent = 0.45), Sundar Nagar East Side 3rd Street W/E (Community hall Road) North Side road (138052R2382, Length = 120, Vent = 0.45), Sundar Nagar East Side 3rd Street W/E (Community hall Road) South Side road (138052R2383, Length = 98, Vent = 0.45), Sundar Nagar 1St Street N/S (Connect To Athimarapatti Road) (138052R2384, Length = 185, Vent = 0.45), North Cotton Road (138039R1781, Length = 630, Vent = 0.45), North Emperor Street (138040L0181, Length = 236, Vent = 0.45), Periyakadi (138040R1801, Length = 234, Vent = 0.45).

File No: E1/1526/2022/(Package-6)

Name of the Bidder/ Bidding Firm /							
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	HGS SS.20.B. Earth work excavating and depositing on bank with initial lead of 10 m & initial lift of 2m in Hard stiff clay, stiff black cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders SS.20B	6100.00	1M3 (One cubic metre)			0.00	INR Zero Only

2	Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification	880.00	1M3 (One cubic metre)			0.00	INR Zero Only
3	Centering for soffits of RCC slabs of plane surface like lintels, beams ,etc.,including strutting 3m high using mild steel sheets of size 90cm X 60cm X and B.G 10 stiffened with M.S angles of size 25mm X 25mm X 3mm laid over silver Oak (C.W) joists of size 10cm X 6.5cm (spaced at about 90cm c/c)and supported dy casurina props of 10cm to 13cm dia (spaced of 75cm C/C) complying with standard specification and directed						
3.01	Wall Centering	17785.00	1M2 (One square metre)			0.00	INR Zero Only
3.02	Slab bottom	520.00	1M2 (One square metre)			0.00	INR Zero Only
4	Suppling and fabricating and placing in position MS (or) R.T.S. bar for reinforcement to all RCC works as per the design given including cost of steel and binding wire also in all floors.	168000.00	1Kg (One Kilogram)			0.00	INR Zero Only

5	Providing and laying in position Standardised Concrete Mix M-20 Grade in accordance with IS 456 - 2000 using 20mm and down graded hard broken granite stone jelly for all RCC items of works with minimum cement content of 3250Kg/10cum and maximum water cement ratio of 0.55 including admixture (Plasticiser / super plasticiser) in recommended proportions as per IS 9103 to accelerate, related setting of concrete, improve workability without impairing strength and durability with about (5.0cum), 7730Kg of 20mm machine crushed stone jelly and with about (3.3 cum), 5156kg of 10 - 12mm machine crushed stone jelly and with about (4.79cum) 7670 kg of sand, but excluding cost of reinforcement grill and fabricating charges centering and shuttering but including laying, vibrating with mechanical vibrators, finishing, curing, etc and providing fixtures like fan clamps in the RCC floor / roof slabs wherever necessary without claiming extra cost etc., complete complying with standard specification and as directed by the departmental officers - The Coarse and Fine aggregates to be used should comply with the requirements of IS standards. (No separate payment will be made by the Department for the excess usage of materials)	2100.00	1M3 (One cubic metre)			0.00	INR Zero Only
6	Providing and Fixing 63 mm dia (6Kg/SqCm) P.V.C. Pipes in weep holes, the rate includes cost of pipe, labour for cutting, packing of concrete, transportation etc., complete as per standard specification	5.00	1Rm (One Running Metre)			0.00	INR Zero Only
7	Dewatering using 3HP to 7.5HP diesel engine pumpset including Hire charges, cost of Diesel, Engine oil, pump operator, labour charges, conveyance of pumpset and fuel to site and back, loading, unloading and any other incidental charges etc., complete.	270.00	1Hrs (One Hours)			0.00	INR Zero Only

8	Supplying and fixing in position 600mm dia FRC manhole cover to suit 600 mm clear opening manhole frame (Extra Heavy Duty) of best approved quality and as per standard specifications etc.,Complete.	68.00	1Nos (One Numbers)			0.00	INR Zero Only
9	Supplying and fixing in position 600mm dia FRC manhole frame to have clear opening of 600mm dia to suit 600mm dia FRC Cover (Extra Heavy Duty) of best approved quality and as per standard specifications etc.,Complete.	68.00	1Nos (One Numbers)			0.00	INR Zero Only
10	Plain Cement Concrete 1:2:4 (one cement, two fine aggregates and four coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard	2.00	1M3 (One cubic metre)			0.00	INR Zero Only
11	Supplying & Fabrication & Placing in position of RCC pre cast slab of 10cm (4") the including all cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	8.00	1M2(One Square metre)			0.00	INR Zero Only
12	Refilling with excavated earth in layers of 30 cm watered well rammed and consolidatred conforming to standard specification including labour charges as directed by Engineer in Charge	910.00	1M3 (One cubic metre)			0.00	INR Zero Only
13	Removal of Excavated Excess Earth away from the site to 2 K.M including loading and transportation charges etc, complete as per standard specification. For 1M3	5200.00	1M3 (One cubic metre)			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					