

## Item Rate BoQ

**Tender Inviting Authority: Commissioner, Thoothukudi City Municipal Corporation**

**Name of Work : Construction of Storm Water Drain at SKSR Colony Road (138011R0680, Length = 285, Vent = 0.6), SKSR Colony park near Road (138011R0681, Length = 80, Vent = 0.9), SKSR Colony W/E Road (138011R0682, Length = 200, Vent = 0.6), SKSR Colony park Road (138011R0683, Length = 140, Vent = 0.6), Ezhil nagar Main 1st cross (138011R0684, Length = 80, Vent = 0.6), Ezhil nagar Main 2nd cross (138011R0685, Length = 80, Vent = 0.6), Ezhil nagar nagar main (138011R0686, Length = 135, Vent = 0.6), Ezhil nagar W/E Road (138011R0687, Length = 50, Vent = 0.6), Selvavinayagapuram main road (138020R1220, Length = 490, Vent = 0.9), Sakthivinayagapuram main road (138011R0662, Length = 350, Vent = 0.9), Sakthivinayagapuram 5th street (138011R0663, Length = 160, Vent = 0.6), Sakthivinayagapuram 4th street (138011R0664, Length = 160, Vent = 0.6), Sakthivinayagapuram 4th street link road (138011R0665, Length = 170, Vent = 0.6), Sakthivinayagapuram 4th Street 2nd Cross Road (138011R0666, Length = 100, Vent = 0.6), Sakthivinayagapuram 2nd street (138011R0668, Length = 125, Vent = 0.6), Sakthivinayagapuram 1st street (138011R0669, Length = 165, Vent = 0.6), Sakthivinayagapuram 1st street link road (138011R0670, Length = 110, Vent = 0.6), VMS Nagar East west road (138014R0893, Length = 150, Vent = 0.6), VMS Naga HP gas opposite (138014R0896, Length = 200, Vent = 0.6), VMS Nagar Santhiya mahal opposite road (138014R0886, Length = 435, Vent = 0.6), VMS Nagar HP Gas front road (138014R0900, Length = 45, Vent = 0.6), VMS Nagar selva vinayagapuram upto vms nagar Road (138014S0312, Length = 100, Vent = 0.6), VMS Nagar selva vinayagapuram upto vms nagar 2nd cross Road (138014R0918, Length = 166, Vent = 0.6), vms nagar south Meelavittan Link Road (138014R0894, Length = 170, Vent = 0.6), HP Gas front Road cross street (138014R0898, Length = 118, Vent = 0.6), Pillaiyar kovil near road (138014R0901, Length = 235, Vent = 0.6), VMS Nagar santhiya mahal front road (138014R0919, Length = 276, Vent = 0.9), Polepettai 60ft main (138012R2524, Length = 710, Vent = 0.9).**

**File No: E1/1526/2022/(Package-1)**

Name of the Bidder/ Bidding Firm /							
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8

1	HGS SS.20.B. Earth work excavating and depositing on bank with initial lead of 10 m & initial lift of 2m in Hard stiff clay, stiff black cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders SS.20B	7662.00	1M3 (One cubic metre)			0.00	INR Zero Only
2	Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification	720.00	1M3 (One cubic metre)			0.00	INR Zero Only
3	Centering for soffits of RCC slabs of plane surface like lintels, beams ,etc.,including strutting 3m high using mild steel sheets of size 90cm X 60cm X and B.G 10 stiffened with M.S angles of size 25mm X 25mm X 3mm laid over silver Oak (C.W) joists of size 10cm X 6.5cm (spaced at about 90cm c/c )and supported dy casurina props of 10cm to 13cm dia (spaced of 75cm C/C) complying with standard specification and directed -						
3.01	Wall Centering	21169.00	1M2 (One square metre)			0.00	INR Zero Only
3.02	Slab bottom	1913.00	1M2 (One square metre)			0.00	INR Zero Only
4	Suppling and fabricating and placing in position MS (or) R.T.S. bar for reinforcement to all RCC works as per the design given including cost of steel and binding wire also in all floors.	199000.00	1Kg (One Kilogram)			0.00	INR Zero Only

5	Providing and laying in position Standardised Concrete Mix M-20 Grade in accordance with IS 456 - 2000 using 20mm and down graded hard broken granite stone jelly for all RCC items of works with minimum cement content of 3250Kg/10cum and maximum water cement ratio of 0.55 including admixture (Plasticiser / super plasticiser) in recommended proportions as per IS 9103 to accelerate, related setting of concrete, improve workability without impairing strength and durability with about (5.0cum), 7730Kg of 20mm machine crushed stone jelly and with about (3.3 cum), 5156kg of 10 - 12mm machine crushed stone jelly and with about (4.79cum) 7670 kg of sand, but excluding cost of reinforcement grill and fabricating charges centering and shuttering but including laying, vibrating with mechanical vibrators, finishing, curing, etc and providing fixtures like fan clamps in the RCC floor / roof slabs wherever necessary without claiming extra cost etc., complete complying with standard specification and as directed by the departmental officers - The Coarse and Fine aggregates to be used should comply with the requirements of IS standards. (No separate payment will be made by the Department for the excess usage of materials)	2485.00	1M3 (One cubic metre)			0.00	INR Zero Only
6	Providing and Fixing 63mm dia (6Kg/SqCm) P.V.C. Pipes in weep holes, the rate includes cost of pipe, labour for cutting, packing of concrete, transportation etc., complete as per standard specification	110.00	1Rm (One Running Metre)			0.00	INR Zero Only
7	Dewatering using 3HP to 7.5HP diesel engine pumpset including Hire charges, cost of Diesel, Engine oil, pump operator, labour charges, conveyance of pumpset and fuel to site and back, loading, unloading and any other incidental charges etc., complete.	328.00	1Hrs (One Hours)			0.00	INR Zero Only

8	Supplying and fixing in position 600mm dia FRC manhole cover to suit 600 mm clear opening manhole frame (Extra Heavy Duty) of best approved quality and as per standard specifications etc.,Complete.	179.00	1Nos (One Numbers)			0.00	INR Zero Only
9	Supplying and fixing in position 600mm dia FRC manhole frame to have clear opening of 600mm dia to suit 600mm dia FRC Cover (Extra Heavy Duty) of best approved quality and as per standard specifications etc.,Complete.	179.00	1Nos (One Numbers)			0.00	INR Zero Only
10	Plain Cement Concrete 1:2:4 (one cement, two fine aggregates and four coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	10.00	1M3 (One cubic metre)			0.00	INR Zero Only
11	Supplying & Fabrication & Placing in position of RCC pre cast slab of 10cm (4") the including all cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	45.00	1M2 (One Square metre)			0.00	INR Zero Only
12	Refilling with excavated earth in layers of 30 cm watered well rammed and consolidated conforming to standard specification including labour charges as directed by Engineer in Charge	945.00	1M3 (One cubic metre)			0.00	INR Zero Only
13	Removal of Excavated Excess Earth away from the site to 2 K.M including loading and transportation charges etc, complete as per standard specification. For 1M3	6720.00	1M3 (One cubic metre)			0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>					