

GRAND SCHEDULE – A
POOLUVAPATTI TOWN PANCHAYAT

Est. No.:		Sold to : Thiru.		
Estimate Amount:	4,613,000	Challan No.	Date.	Date.
EMD.Amount :				
Tender Date & Time:				

Schedule of rates and approximate quantities to accompany the tender for the work of

Name of the Work : Construction of Cement concrete road at Vadivelampalayam Mayanam road in Pooluvapatti Town Panchayat.

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.

- b) It is to be expressly understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Town Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.

- c) The material required for the works must be supplied by the contractor and of the approved quality

CONTRACTOR

GRAND TENDER SCHEDULE

Name of work : Name of the Work : Construction of Cement concrete road at Vadivelampalayam Mayanam road in Pooluvapatti Town Panchayat.

Estimate amount: 4,613,000

Sl. No.	Probable Quantity		Description of Work	MORTHNo.	Rate		Unit	Amount in rupees
					In Figures	In Words		
11			Supplying and erecting centering to sides and soffits including supports and strutting with necessary cross bracing for plain surface such as RCC slabs rectangular beams all beams lintels etc., centering for soffits upto 3 meter height using mild steel sheet of size 90 cm x 60 cm x 10 mm gauge with MS angles of size 25mm x 25mm x 3mm laid over silver oak (CW) joists of size 10cm x 6cm spaced upto 90cm c/c and casurina props or 10 cm to 13 cm dia spaced at 0.750 cm c/c complying with standard specifications as per TNDSS NO : 30 & 86.					
	69.00	m2	below 1.00m				1 m ² (One Square Metre)	

CONTRACTOR

Sl. No.	Probable Quantity		Description of Work	MORTHNo.	Rate		Unit	Amount in rupees
					In Figures	In Words		
	880.00	m2	Above 1.00m				1 m ² (One Square Metre)	
12	221.50	m3	Plain Cement Concrete 1:3:6 Mix (one part cement, three part Msand and six part of aggregate) using 20 mm size ISS HBG metal from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing. Laying and curing etc., complete as per TNDSS NO: 28 & VI (S2) VI (S5A) VII standard specifications as directed by Engineer incharge.				1 m ³ (One Cubic Metre)	
13	30.00	m4	Supply and Fixing of 15mm thick Bitumen Pad including cost and conveyance of all materials to site and all labour charges etc., complete as per stand specification.				2 m ³ (One Cubic Metre)	
14		m2					1 m (One sQUARE Metre)	

CONDITION : Bitumen will not be supplied by department. Contractors should make their own arrangements.

Assistant Engineer
Perur group
Coimbatore zone

Assistant Executive Engineer
Coimbatore zone

Executive Engineer
Coimbatore zone

CONTRACTOR