

PART A - TECHNICAL BID

TENDER DOCUMENTS FOR INTERIOR FURNISHING WORK **FOR UBI - OLD PADRA ROAD BRANCH (EXISTING PREMISES),** **UBI - VADODARA REGION.**

1	TENDER ISSUED TO (Name & Address of the Contractor)	M/S.....
2	EMD COST	Rs. 20,000/- (Twenty Thousand Only)
3	TENDER FEES	Rs. 1,000/- (One Thousand Only)
4	PROJECT ARCHITECTS	M/S. SHAW ARCHITECTS, SF-218, SAMANVAY SILICON, NR. DAIRY DEN CIRCLE, SAYAJIGUNJ, VADODARA – 390005, GUJARAT.
5	ARCHITECT'S CONTACT DETAIL	M: +91-9898213973 E-MAIL: shawvijendra@gmail.com
6	OWNER	UNION BANK OF INDIA - VADODARA REGIONAL OFFICE, 2 ND FLOOR, UBI BHAVAN, STATION ROAD, SAYAJIGUNJ, VADODARA-390005, GUJARAT.

INDEX

1. NOTICE OF INVITATION TO TENDER
2. GENERAL RULES AND INSTRUCTIONS FOR THE GUIDANCE OF TENDERERS AND FORM OF TENDER
3. ARTICLES OF AGREEMENT
4. SPECIAL INSTRUCTIONS TO TENDERERS
5. SAFETY CODE AND MODEL RULES FOR PROTECTION OF HEALTH AND SANITARY ARRANGEMENTS FOR WORKERS.
6. PREAMBLE AND SPECIFICATIONS
7. APPENDIX, IF ANY
8. SPECIFICATIONS AND WORKMANSHIP
9. SCHEDULES
10. MODE OF MEASUREMENTS
11. MANDATORY INFORMATION (TO BE FILLED BY CONTRACTOR)
12. BILL OF QUANTITIES
13. DRAWINGS

NOTICE INVITING TENDER (NIT)

UNION BANK OF INDIA - REGIONAL OFFICE VADODARA Invites sealed tenders from the **INTERIOR FURNISHING WORK CONTRACTORS ON UNION BANK'S APPROVED PANEL OF VADODARA REGIONAL OFFICE ONLY UNDER APPROPRIATE CATEGORY (5 Lacs and Above)** for the work mentioned below.

1	Name of work	INTERIOR FURNISHING WORKS AT EXISTING PREMISES OF UBI-OLD PADRA ROAD BRANCH UNDER UBI - VADODARA REGION.
2	Date of Issue of tender documents	02 / 04 / 2022 at 11:00 a.m.
3	Last date of tender collection/submission	12 / 04 / 2022 at 12:00 p.m.
4	Date & Time of opening of tender	12 / 04 / 2022 at 02:30 p.m.
5	Mode & Place of submission of bids	By RPAD or Speed Post or courier or by hand delivery only addressed to: THE REGIONAL MANAGER, UNION BANK OF INDIA - VADODARA REGIONAL OFFICE, 2ND FLOOR, UBI BHAVAN, STATION ROAD, SAYAJIGUNJ, VADODARA-390005, GUJARAT.
6	Date of commencement	02 days from the date of issue of work order.
7	Date of completion of work	30 days from the date of issue of work order.
8	Period for settlement of final bill	30 days from date of issue of completion certificate by the Architect.
9	Initial Security Deposit (ISD)	The amount of Initial Security Deposit shall be 2% of the accepted value of the tender including the Earnest Money Deposit.
10	Total Security Deposit	TSD shall be 5% of contract value which will be deducted from the final bill of the contractor by way of retention amount. TSD will be refunded to the contractor on successful completion of defect liability period.
11	Tender Cost (To be submitted in Envelope-1)	Rs. 1,000/- (One Thousand Only) to be submitted in the form of D.D. (o n l y) in favour of Union Bank of India, Payable at VADODARA valid for 90 days. <i>(Exempted for NSIC/MSME for valid certificate. Certificate to be attached.)</i>
12	Earnest money deposit (To be submitted in Envelope-1)	Rs. 20,000/- (Twenty Thousand Only) to be submitted in the form of D.D. (o n l y) in favor of Union Bank of India, Payable at VADODARA valid for 90 days. <i>(Exempted for NSIC/MSME for valid certificate. Certificate to be attached.)</i>
13	Release of Retention Money/ Earnest money	The Earnest money deposited shall not carry any interest and will be refunded to unsuccessful tenderers after allocation of work order. The Earnest money of successful tenderer will be release after completion of work and certification of final bill. Retention & Security money after 14 days from defect liability period without any interest.
14	Sign and Stamp	<u>All the pages</u> are to be stamped and signed by the contractors.
15	Approved Brands	Only <u>approved brands</u> of materials should be used for work.
16	Specification of Materials	<u>Specification of Materials</u> is as per Tender Technical Bid.
17	Articles of Agreement	To be prepared in consultation with the Legal Department of the Bank. The Central Agreement is composite summary of all the tender which reflects extracts of all tender conditions. The form and conditions in the Article of Agreement should be in line with the terms and conditions accepted in tender Document / Addendum / Work order etc. The same shall be verified before execution of the

		Agreement. No conditions to be added in contract unless and otherwise accepted by both parties during tendering process.
18	Liquidated damages for non-completion of work within the date of completion	1% per week subject to maximum of 10% of contract value inclusive of Sundays and Holidays.
19	Defect liability period	12 months from the date of completion certificate issued by the Bank Architect.
20	Validity of Tender	90 days from the date of Price Part of Tender.
21	Tender can be Downloaded from	UBI website http://unionbankofindia.com under Tender Section.
22	Bank reserves the right to ask for bills/invoices of the material purchased by the Contractor along with the payment details.	
23	Bank may accept the tender either in complete or in parts. Bank also reserves the right to split the tender.	
24	Interested bidder may obtain further information from the office of consultant / Bank Architect.	
25	Bank reserves the right to reject wholly or part of any or all tenders received without Assigning any reason whatsoever, Also Bank reserves the right to split the work and place the order to more than one party.	
26	Any Freak Rate of Individual Item on Higher Side Are Liable for Negotiation	
27	Any Contractor which is empanelled in more than one category (i.e, Furniture/Electrical/Air Conditioning) <u>can only compete only in one category</u> . If applied for more than one category, then tender will be rejected.	
28	Rates quoted & agreed by the tenderer shall remain firm throughout the contract period (Including authorized extension). Rates quoted shall be inclusive of all taxes, duties, levies, royalties & other incidental / other Industrial charges etc. However, GST Tax shall be paid by the bank extra as applicable to work contract tax as per actual.	
29	Running bills each not more than 4.0 lacs shall be paid. Final Bill will be paid against the final payment certificate on submission detailed final bills submitted by the contractor to the Architect on successful Completion of the work.	
30	All pages of Tender Documents and attachments by Bidder will duly signed and stamped or else it will be subjected for rejection.	

UBI has right to accept/ reject any/ all tenders without assigning any reasons.
(For and on behalf of Union Bank of India)

THE REGIONAL MANAGER,
UNION BANK OF INDIA - VADODARA REGIONAL OFFICE,
2ND FLOOR, UBI BHAVAN, STATION ROAD,
SAYAJIGUNJ, VADODARA-390005, GUJARAT.

Date: 02/ 04/ 2022

IMPORTANT POINTS:

1. Technical prequalification will be based on the mandatory information and supporting documents submitted along with the tender documents as well as Architect/Bank's scrutiny of the same or inspection of work carried out by the tenderer.
2. The Union Bank of India, reserves the right that without assigning any reason there of:
 - (a) To accept or reject any tender in whole or in part.
 - (b) To increase or decrease the quantities of any item and tendered has to execute the same at the rate quoted.
3. Tenderer are requested to read the tender documents, general conditions, special conditions, drawing, specifications, schedule of quantities, etc. carefully and offer most competitive rate after visiting site. The clause of Notice Inviting tender prevails over general terms and special terms of contract.
4. The date of completion of job is the essence to this contract. The contractors are therefore requested to complete the job in the stipulated time. Any deviation with respect to time or specification Bank prejudice has right to:
 - (a) Cancel / Revoke the order.
 - (b) Impose penalty up to 10 % of the total value of job.
5. Contractor in their own interest are advised to visit the site & get themselves familiarize in the prevailing situations before submitting their rates. No claim whatsoever for ignorance, misunderstanding shall be entertained later.
6. The proposed work is to be done in the working branch on ground floor, hence contractor has to plan his work so as to general working of the branch is not affected. He has to work after business hours & also during the night.
7. The contractor shall be responsible for making good in expeditions & workman like manner. Any defects, which may be found within one years of the handing over the premises, put to beneficial use. In case contractor fails to do so, the same would be got done at his cost & risk. The cost incurred by the bank shall be deducted from the retention money or any other dues.
8. Rates quoted shall be inclusive of all taxes, levies, duties & all charges such as freight, insurance, octroi, loading/unloading, unpacking & moving the position in site, etc. for complete item.
9. The schedule of quantities is only approximate & all the work executed shall be paid for in accordance with the actual measurements as per relevant part of IS : 1200 : 1974 or otherwise provided.
10. In case of any dispute, the same shall be referred to court at VADODARA and its decision shall be final & binding on both the parties.
11. An item rate tender containing percentage below / above will be summarily rejected. However, if the Tender voluntarily offers rebate for payment with in stipulated period, this may be considered.
12. The tender documents shall be duly filled in and signed by the tenderer and shall be addressed (in sealed cover) to the office of: **THE REGIONAL MANAGER, UNION BANK OF INDIA - VADODARA REGIONAL OFFICE, 2ND FLOOR, UBI BHAVAN, STATION ROAD, SAYAJIGUNJ, VADODARA-390005, GUJARAT.** The full name and address of the tenderer and name of the work shall be written on the cover.
13. Unit rates shall be quoted in English in figures as well as in words with reference to each item and for all items shown in the attached schedule of quantities. The amount of each item should be worked out.
14. All entries in the documents shall be clearly written and shall be in ink. corrections if any shall be clearly made any duly signed and dated by the tenderer erasing and over writings and shall not be permitted and the tender liable for rejection.
15. The tender shall sign and every page of the tender documents including the layout drawings.
16. Each tender shall be signed by the tenderer with his usual signature. Tender by Partnership of Hindu joint family firm may be signed in the firm's name by one of the partners of the Karta or Manager as the case may be or any other duly authorized representative followed by the name and designation of the person so signing. An attested copy of the partnership firm shall also be attached. Tender by a shall be signed with the name of the company by persons authorized in

this behalf and power of attorney or other satisfactory proof showing the person signing the tender as the authorized person to do such documents on behalf of the company is duly authorized to do so shall accompany the tender.

17. Unless otherwise specified all the rates and prices in the tender shall cover sales taxes, octroi, vat, other taxes and duties, and transportation, sales tax on work contract etc.

18. Tender not containing the full particulars as mentioned above or as called for in the special conditions is liable to summarily rejection.

19. With their quotations the tenderer shall sign all the schedules specifications, special conditions, etc. in taken of acceptance hereof. The signature on the tender schedule alone shall also be deemed to be taken as acceptance of all these.

20. The unsealed tenders, tenders not super scribed as the prescribed tender documents, conditional and unsigned tenders, tenders containing absurd rates and amounts, tenders that are incomplete or otherwise considered defective are liable to be rejected.

21. In the event, there are two or more parties between whom the work has been split, the contractor carrying out relevant work entrusted to him shall work in close coordination without causing any delay or hindrance to other agencies. Bank has the right to omit at his discretion one or more items of work when placing the order.

22. The work shall be deemed to have commenced from the date on which the contractor takes over the site or issue of work orders whichever is earlier. The site will be handed over to the contractor only on submission of initial security deposit.

23. The contractor shall give a program for the execution of the work during the total contract period and get it approved by the Bank and the Architect. In case of delay in progress of work at any stage, the Bank shall issue the contractor a memo in writing pointing out the delay in progress and asking the contractor to explain the causes for the delay within 3 days of receipt of the above. The Bank reserves the right to terminate the contract and forfeit the security deposit if satisfactory explanation is not offered by the contractor for delay in execution of work.

24. It will be obligatory on the part of the tenderer to sign on each & every page of the tender & all components of the tender. Conditional tender shall be summarily rejected.

25. The samples of all the material & work item shall be got approved from the Architect or his representative before proceeding further on the work.

26. The drawing contains sketches showing salient features details at the various scales indicating extent of work & specifications to be followed. These can be modified by the bank from time to time in accordance with technical requirements at the site.

27. Any damage done to the property of the bank during execution of the work shall be responsibility of the contractor & it shall be made good by him, at his cost to the entire satisfaction of Architect/Bank.

28. The Architects shall have full power to get the material or workmanship etc. inspected & tested by an independent agency for its soundness & adequacy at the cost of contractor.

29. The contractor shall examine all drawings before quoting & commencing of actual work & report to the Architect/Bank any discrepancies for omission & shortcomings in the drawings.

30. The work shall be of highest standard both as regard to material & workmanship. Modern tools & first-class latest techniques shall be employed for its execution.

31. The work shall be done as per accordance with the IBA guidelines.

Signature of contractor with seal

SPECIAL TERMS AND CONDITIONS

1	Limit of variation	100% without any change in price if work is done within six months of the contract and with prior consent of Architect / Consultant.
2	Additional items	For items where unit rates are not available, contractor shall provide proper cost break-up and proceed only after approval/consent. Any sample to be made for approval shall be at the Contractor's cost.
3	Validity of tender	Three months after the opening of the tender.
4	Rules/ Regulations	The contractor shall have their responsibility of complying with the local shops/establishments Act and other labor / minimum wages Act and shall keep all such records/ accounts on payment of wages / attendance as deemed necessary.
5	Arbitration	As per the standard arbitration clause under the jurisdiction of VADODARA.
6	Organization	The contractor shall employ competent / qualified supervisor /Engineer-in-charge who shall be responsible for the day to day work and coordinate as necessary with the Architect's supervisor. Any workman found guilty of misconduct/theft shall remove from the site.
7	Damage to property	Any damage to the Bank's property during the work period will be recovered from the contractor as per the valuation submitted by Architect.
8	Deduction	Tax at source as per Act.
9	Terms of payment	Payment after completion of Project.
10	Billing Procedure	All measurements shall be recorded in Duplicate on standard measurement sheets Prepared jointly by the Architect's Site Engineer & the Contractor's Representatives duly signed by them. All Bills shall be submitted along with this Checked Measurement sheets.
11	Time schedule of work	The Contractor must submit before the Commencement of work, a Bar chart showing the date of commencement & the date of completion of each item of Work as mentioned in the Schedule of Quantities.
12	Release of TSD	100% after the Defect liability period. Retention money will not bear any interest.
13	General	The rates should be quoted considering necessary Scaffolding & staging work, Removal of debris as & when necessary, In view of restriction of Local concern Authority & all type of Lab test.
14	Site Location	The aforesaid work needs to carry out at OLD PADRA ROAD in Gujarat State.
15	Workmen Insurance	Contractor shall submit workmen compensation policy of each individual workmen.

FORM OF TENDER

(On the Letterhead of Tenderer)

**THE REGIONAL MANAGER,
UNION BANK OF INDIA - VADODARA REGIONAL OFFICE,
2ND FLOOR, UBI BHAVAN, STATION ROAD,
SAYAJIGUNJ, VADODARA-390005, GUJARAT.**

Dear Sirs Ref:

Having examined the drawings, specifications, design and schedule of quantities relating to the works specified in the memorandum hereinafter set out and having visited and examined the site of the works specified in the said memorandum and having acquired the requisite information relating thereto as affecting the tender. I/We hereby offer to execute the works specified in the said memorandum at the rates mentioned in the attached schedule of quantities and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in condition of tender, the Articles of Agreement special conditions, schedule of quantities and conditions of contract and with such material as are provided for, by and in all other respects in accordance with such conditions so far as they may be applicable.

MEMORANDUM

1.
A Description work: **INTERIOR FURNISHING WORKS IN UNION BANK OF INDIA OLD PADRA ROAD BRANCH, VADODARA REGION.**
B Earnest money: **Rs. 20,000/-**
C Security Deposit: 2 % of the accepted tender amount less earnest money
D Percentage if any to be deducted from bills: 5% (Five percent) from the bills of the contractors excluding earnest money and initial security Deposit.
E Time allowed for completion of the work: **30 days.** From the date of commencement of work
F. Liquidated damage: 1 % of contract value per week. Maximum 10 % of the contract value.
2. We undertake to complete and deliver the whole of the works comprised in the contract with in the time stated in the schedule A to the general conditions of the contract.
3. We have independently considered the amount of liquidated damages in the schedule A to the conditions of the conditions of the contract and agree that it represents fair estimated the loss likely to be suffered by you in the event of the works not being completed in time.
4. If our tender is accepted, we will be required to furnish the security deposit of the contract for the due performance of the contract as specified in the general conditions of the contract & NIT.
5. We agree to abide by this tender for the period of 90 days from the date fixed for opening the second cover (i.e. price bid) and it shall remain binding upon and may be accepted at time before expiry of period.
6. Unless and until a formal agreement is prepared and executed this tender together with your written acceptance there of shall constitute a binding contract between us.
7. We understand that you are not bound to accept the lowest or any tender you may receive.
8. Should this tender be accepted, I/We hereby agree to abide by and fulfill the terms and provisions of the said conditions of contract annexed to so far as they may be applicable or in default thereof to forfeit and pay to the Union Bank of India, Vadodara the amount mentioned in the said conditions.

9. We are enclosing the Bank Draft for a sum of **Rs. 20,000/-** as Earnest money in favor of Union Bank of India, payable at VADODARA Which amount will not bear any interest. Should we fail to execute the contract when called upon to do so, I/We do hereby agree that the Union Bank of India shall forfeit this sum.

10. The details of plant, machinery, major tools, equipment employees list of such major works executed technical personal along with the copies of last 3 years I.T. assessment orders are enclosed for your perusal and consideration.

11. Our Bankers are:

12. The names of the partners of our firm are:

Name of the Partner of the firm authorized to sign

OR

Name of person having power of attorney to sign the contract.

(Certified true copy of the power of attorney should be attached.)

(Signatures and address of Witnesses.)

Yours faithfully,

Signature of contractor.

(1)

(2)

List of enclosures:

(1) PERT CHART

(2) Please enclose separate sheets if required.

Signature of the Contractor with Seal

ARTICLES OF AGREEMENT

Articles of Agreement made this _____ day of _____ between **THE REGIONAL MANAGER, UNION BANK OF INDIA - VADODARA REGIONAL OFFICE, 2ND FLOOR, UBI BHAVAN, STATION ROAD, SAYAJIGUNJ, VADODARA-390005, GUJARAT.** Hereinafter called the Bank which expressions shall include its successors and assigns of the one part and _____ (name & address of contractor) hereinafter called the "Contractor" which expression shall include the successors and assigns of the other part.

WHEREAS the Bank is desirous of the work of **INTERIOR FURNISHING WORK AT UBI-OLD PADRA ROAD BRANCH, VADODARA REGION** and has caused drawings, specifications and schedule of quantities etc. describing the works to be prepared by ARCHITECT: **SHAW ARCHITECTS** AND WHEREAS for the said interior of UBI-OLD PADRA ROAD Branch under local regional office of Union Bank of India at VADODARA. Terms & Conditions, Specifications and the Schedule of items quantities etc., have been signed by and on behalf of the parties hereto.

AND WHEREAS the Contractor has agreed to execute upon, subject to the conditions set forth herein and Schedule of Items and quantities, General & Special Conditions of Contract, specifications etc. contained in the tendered documents including all correspondences exchanged by or between the parties from the submission of tender till the award of work, both letters inclusive, (all of which are collectively hereinafter referred to as "the said conditions"), details of which are described in the schedule attached hereto, the works shown upon the said drawings and/or described in the said specification and included in the schedule of items and quantities at the respective rates therein set forth amounting to the sum as therein arrived at or such other sum shall become payable there under arrived at or such other sum as shall become payable there under (hereinafter referred to as "the said contract amount").

NOW IT IS HEREBY AGREED AS FOLLOWS:

1. In consideration of the said contract amount to be paid at the time and in the manner set forth in the said conditions, the contractor shall upon and subject to the said conditions execute and complete the work shown in the said drawings and described in the said specifications and the schedule of items and quantities, as per the terms and conditions contained in the said conditions.
2. The Bank shall pay the Contractor said contract amount, or such other sum as shall become payable, at the time and in the manner specified in the said conditions.
3. The Architects in the said condition shall mean the said ARCHITECTS M/s SHAW ARCHITECTS, SF-218, SAMANVAY SILICON, OPP. KALYAN HOTEL, NR. DAIRY DEN CIRCLE, SAYAJIGANJ, VADODARA. In the event of their ceasing to be the Architects for the purpose of this contract for whatever reason, such other person or persons as shall be nominated for that purpose by the Bank, provided always that no person subsequently appointed as Architects under this contract shall be entitled to disregard or over rule any previous decisions or approvals or directions given or expressed in writing by the Architects for the time being.
4. The said general condition, Special condition, technical drawings, Notice Inviting Tender, specifications, Guarantee, Instruction to Tenderers Price Bid (Schedule of Quantities), Correspondences, Letter of Acceptance, Agreements and Appendices there to, contained in the tendered documents/said conditions shall be read and considered as forming part of this Agreement and the parties hereto shall respectively abide by, submit themselves to the said conditions and perform the agreements on their part respectively in the said conditions contained therein.
5. The plans, agreements and documents mentioned herein shall form the basis of this contract. This contract is neither a fixed Lump Sum contract but is a contract to carry out the work in respect of the **INTERIOR FURNISHING WORK AT UBI - OLD PADRA ROAD BRANCH, VADODARA REGION** as per the scope described and to be paid for according to actual measured quantities at the rates contained in the Schedule of Rates and/or negotiated rates and Probable quantities or as provided in the said conditions.

6. The Bank reserves to itself the rights of altering the specifications and nature of the work by adding to or omitting any items of work or having portions of the same carried out without prejudice to this contract.

7. (a) The Contractors represent that they have experience and competent staff which will enable them to ensure proper quality check on the materials, whether brought by the contractors or supplied by the Bank to the contractors, and which will ensure that the contractor will carry out proper tests as required by the specifications and will supervise the day to day working and execution of the contract work.

(b) If the contractors have any doubt about the quality of the materials or any difficulty in supervision of the day to day work it shall be duty of the contractors to report the matter in writing forthwith to the Bank and for the time being suspend that portion of the work about which difficulty is experienced, and the contractors will abide by the directions given by the Bank.

(c) The contractors are aware that the Bank will not give day to day supervision but will periodically supervise and the contractor has to perform their obligations under the instructions given to him periodically and under sub clauses (a) and (b) above.

(d) The contractors covenant and warrant that completed items of work as well as the entire work on completion will be in conformity with the specifications and the terms and conditions contained in the said conditions and will be of contract quality and description.

8. Time shall be considered as the essence of this contract and the contractor hereby agrees to commence the work on the day on which he is instructed to take possession of the site or from the fourteenth day after the day of issue of formal Work Order as provided for in the said conditions whichever is later and to complete the entire work within **30 days** subject nevertheless to the provisions for the extension of time.

9. All payments by the Bank under this contract will be made only at **UBI, VADODARA REGION**. Any dispute arising under this Agreement shall be referred to arbitration in accordance with the stipulation laid down in the general conditions of contract.

10. The contents of this agreement have been read by the contractor.

IN WITNESS WHEREOF the Bank and the Contractor have set their respective hands to these Presents and two duplicates hereof the day and year first herein above written (If the Contractor is a Partnership Firm or an Individual).

IN WITNESS WHEREOF the Bank has set its hands to these presents through its duly authorized official and the contractor has caused its common seal to be affixed hereunto and the said duplicates have/has caused these presents and the said two duplicates hereof to be executed on its behalf, the day and year first herein above written (If contractor is a Company).

Signature Clause:

Signature clause:

SIGNED AND DELIVERED

By the hand of Shri _____ (Name and Designation)

In presence of _____

1. _____

Address _____

2. _____

Address _____

(Witness)

SIGNED AND DELIVERED by _____ (If the Contractor is a Partnership Firm or an individual , should be signed by all partners or by duly authorized person on behalf of all partners)

(1) _____



Address _____

(2) _____

Address _____

(Witness)

THE COMMON SEAL OF _____ was here into affixed pursuant to the resolution By Board of Directors at the Meeting held on _____ (If the Contractor signs under its common seal, the Signature Clause should tally with the sealing clause in the Articles of Association)

SIGNED AND DELIVERED by

(1) _____

(2) _____

1) _____

Address _____

(2) _____

Address _____

(Witness)

SIGNED AND DELIVERED by _____ (If the Contractor has signed by the hand of Power of Attorney , whether a Company or Individual)

(1) _____

Address _____

(2) _____

Address _____

(Witness)

GENERAL CONDITIONS OF CONTRACT

1.0 DEFINITIONS

“Contract” means the documents forming the tender and the acceptance thereof and the formal agreement executed between Union Bank of India (client) and the Contractor, together with the documents referred therein including these conditions, the specifications, designs, drawings and instructions issued from time to time by the Architects/Bank and all these documents taken together shall be deemed to form one contract and shall be complementary to one another.

1.1 In the contract the following expressions shall, unless the context otherwise requires, have the meaning hereby respectively assigned to them.

1.1.1 ‘UBI shall mean Union Bank of India (client) having its **Regional Office at 2ND Floor, Ubi Bhavan, Station Road, Sayajigunj, Vadodara-390005, Gujarat.** and includes the Client’s representatives, successors and assigns.

‘Architect/consultants’ shall mean APPOINTED ARCHITECTS: Shaw Architects having its Head Office at SF-218, Samanvay Silicon, Sayajigunj, Vadodara-3900 05 and it shall include its representative, successors and assigns.

1.1.2 ‘Site Engineer’ shall mean an Engineer appointed by the Bank or the Architect or by the Bank through Architect.

1.1.3 As their representative to give instructions to the contractor.

1.1.4 ‘The Contractor’ shall mean the individual or firm or company whether Incorporated or not, undertaking the works and shall include legal personal representative of such individual or the composing the firm or company and the permitted assignees of such individual or firm or company.

The expression ‘Works’ or ‘Works’ shall mean the permanent or temporary work described in the ‘Scope of Work’ and/or to be executed in accordance with the contract and includes materials, apparatus, equipment’s, temporary supports, fittings and things of all kinds to be provided, the obligations of the contractor hereunder and work to be done by the contractor under the contract.

1.1.5 ‘Engineer’ shall mean the representative of the Architect/Consultant.

1.1.6 ‘Drawings’ shall mean the drawings prepared by the Architects and issued by the Engineer and referred to in the specifications and any modifications of such drawings as may be issued by the Engineer from time to time ‘Contract value shall mean the value of the entire work as stipulated in the letter of acceptance of tender subject to such additions thereto or deductions there from as may be made under the provision herein after contained.

1.1.7 ‘Specifications’ shall mean the specifications referred to in the tender and any modifications thereof as may time to time be furnished or approved by the Architects/consultant. “Month” mean calendar month.

1.1.8 ‘Week’ means seven consecutive days.

1.1.9 ‘Day’ means a calendar day beginning and ending at 00 hr and 24 hrs respectively.

CLAUSE

1.0 TOTAL SECURITY DEPOSIT

Total Security Deposit shall be as defined in “NIT”.

a) EARNEST MONEY DEPOSIT

The tenderer shall furnish EMD as specified in the NIT in the form of Demand draft drawn in favor of the Union Bank of India on any Scheduled Bank. No tender shall be considered unless the EMD is so deposited in the required format. No interest shall be paid on this EMD. The EMD of the unsuccessful tenderer shall be refunded soon after the decision to award the contract is taken without interest. The EMD shall stand absolutely forfeited if the tenderer revokes his tender at any time during the period when he is required to keep his tender open for acceptance by the UBI or after it is accepted by the UBI the contractor fails to enter into a formal agreement or fails to pay the initial security deposit as stipulated or fails to commence the work within the stipulated time.

b) INITIAL SECURITY DEPOSIT (ISD)

The amount of ISD shall be 2% of accepted value of tender including the EMD. Balance of ISD (i.e. excluding EMD) is to be submitted in the form of D/D drawn on any scheduled Bank and shall be deposited within 15 days from the date of letter of acceptance of tender.

c) RETENTION MONEY

The retention percentage (i.e. deduction from interim bill) shall be 8% of the gross value of each interim bill. The maximum amount of retention money shall be the balance amount of the Total Security Deposit.

50% of the retention amount is refunded to the contractor on completion subject to the following:

- i. Issue of Virtual Completion Certificate by the Architect / Premises Department.
- ii. Contractor's removal of his materials, equipment, labour force, temporary sheds / stores etc. from the site, (excepting for a small presence required if any for the Defect Liability Period and approved by the Bank).

The remaining 50% of the amount may be refunded 14 (fourteen) days after the end of defects liability period provided, he has satisfactorily carried out all the works and attended to all defects in accordance with the conditions of the Contract, including site clearance.

2.0 LANGUAGE

The language in which the contract documents shall be drawn shall be in English.

3.0 ERRORS, OMISSIONS AND DISCREPANCIES

In case of errors, omissions and/or disagreement between written and scaled dimensions on the drawings or between the drawings and specifications etc., the following order shall apply:

- i) Between scaled and written dimension (or description) on a drawing, the latter shall be adopted.
- ii) Between the written or shown description or dimensions in the drawings and the corresponding one in the specification the former shall be taken as correct.
- iii) Between written description of items in the specifications and description in bills of quantities of the same former shall be adopted.
- a) In case of difference between rates written in figures and words, the rate in word shall prevail.
- b) Between the duplicate/subsequent copies of the tender, the original tender shall be taken as correct.

SCOPE OF WORK

The contractor shall carryout complete and maintain the said work in every respect strictly in accordance with this contract and with the directions of and to the satisfaction of the Bank to be communicated through the Architect/Consultant. The Architect/Consultant at the directions of the Bank from time to time, issue further drawings and/or written instructions, detail directions and explanations which are hereafter collectively referred to as the Architect/Consultant's instructions in regard to the variation or modification of the design, quality or quantity of work or the addition or omission or submission of any work. Any discrepancy in the drawings or between the BOQ and/or drawings and/or specifications, the removal from the site of any material brought thereon by the Contractor and any submission of any other materials thereof the removal and or re-execution of any work executed by him, the dismissal from the work of any person employed/engaged there upon.

5.0

(I) LETTER OF ACCEPTANCE:

Within the validity period of the tender, the Bank shall issue a letter of acceptance either directly or through the Architect/Consultant by registered post or otherwise depositing at the address of the contractor as given in the tender to enter into a Contract for the execution of the work as per the terms of the tender. The letter of acceptance shall constitute a binding contract between the UBI and the contractor.

(II) CONTRACT AGREEMENT:

On receipt of intimation of the acceptance of tender from the UBI/Architect the successful tenderer shall be bound to implement the contract and within fifteen days thereof. He shall sign an agreement on a non- judicial stamp paper of appropriate value. The successful contractor may be required to sign agreement as may be drawn up to suit local conditions and shall pay for all stamps and legal expenses, incidental thereto.

6.0 OWNERSHIP OF DRAWINGS:

All drawings, specifications and copies thereof furnished by the UBI through its Architect/Consultants are the properties of the UBI. They are not to be used on other work.

7.0 DETAILED DRAWINGS AND INSTRUCTIONS:

The UBI through its Architect/Consultants shall furnish with reasonable promptness additional instructions by means of drawings or otherwise, necessary for the proper execution of the work. All such drawings and instructions shall be consistent with the contract document, true developments thereof and reasonably inferable there from.

The work shall be executed in conformity therewith and the contractor will prepare a detailed program schedule indicating therein the date of start and completion of various activities on receipt of the work order and submit the same to the UBI through its Architect/Consultant.

8.0 COPIES OF AGREEMENT:

Two copies of agreement duly signed by both the parties with the drawings shall be handed over to the contractors.

9.0 LIQUIDATED DAMAGES:

If the contractor fail to maintain the required progress or to complete the work and clear the site including vacating their office on or before the contracted or extended date or completion without justification in support of the cause of delay, he may be called upon without prejudice to any other right of remedy available under the law to the UBI on account of such breach to pay a liquidated damages as mentioned in NIT.

10.0 MATERIALS, APPLIANCES AND EMPLOYEES:

Unless or otherwise specified the contractor shall provide and pay for all materials, labor, water, power, tools, equipment, transportation and any other facilities that are required for the satisfactory execution and completion of the work. Unless or otherwise specified all materials shall be new and both workmanship and materials shall be of best quality. The contractor shall at all times enforce strict discipline and good order among his employees and shall not employ on the work any unfit person or any one not skilled in the work assigned to him. Workman whose work or behavior is found to be unsatisfactory by the UBI/Architect/Consultant shall be removed from the site immediately.

11.0 PERMITS, LAWS AND REGULATIONS:

Permits and licenses required for the execution of the work shall be obtained by the contractor at his own expenses. The contractor shall give notice and comply with the regulations, laws and ordinances, rules applicable to the contract. If the contractor observes any discrepancy between the drawings and specifications, he shall promptly notify the UBI in writing under intimation of the Architect/Consultant. If the contractor performs any act which is against the law, rules and regulations he shall meet all the costs arising there from and shall indemnify the UBI any legal actions arising there from.

12.0 SETTING OUT WORK:

The contractor shall set out the work and shall be responsible for the true and perfect setting out the same and for the correctness of the positions, levels, dimensions, and alignment of all parts thereof and got it approved by the Architect/Consultant before proceeding with the work at any time any error in this respect shall appear during the progress of the works, irrespective of the fact that the layout had been approved by the Architect/Consultant the contractor shall be responsible for the same and shall at his own expenses rectify such error, if so, required to satisfaction of the UBI.

13.0 PROTECTION OF WORKS AND PROPERTY:

The contractor shall continuously maintain adequate protection, of all his work from damage and shall protect the UBI's properties from the injury or loss arising in connection with contract. He shall make good any such damage, injury, loss, except due to causes beyond his control and not due to his fault or negligence.

He shall take adequate care and steps for protection of the adjacent properties. The contractor shall take all precautions for safety and protections of his employees on the works and shall comply with all applicable provisions of Govt. and local body's safety laws and building codes to prevent accidents or injuries to persons or property on about or adjacent to his place of works. The contractor shall take insurance cover as per clause at his own cost. The policy may be taken in joint names of the contractor and the UBI and the original policy may be lodged with the UBI.

14.0 INSPECTIONS OF WORK:

The UBI/Architect/Consultant or their representatives shall at all reasonable times have free access to the work site and/or to the workshop, factories, or other places where materials are laying or from where they are obtained and the contractor shall give every facility to the UBI/Architect/Consultant and their representatives necessary for inspection and examination and test of the materials and workmanship. No person unless authorized by the UBI/Architect/Consultant except the representative of Public authorities shall be allowed on the work at any time. The proposed work either during its construction stage or its completion can also be inspected by the Chief Technical Examiner's organization a wing of Central Vigilance commission.

15.0 ASSIGNMENT AND SUBLETTING:

The whole of work included in the contract shall be executed by the contractor and he shall not directly entrust and engaged or indirectly transfer, assign or underlet the contract or any part or share thereof or interest therein without the written consent of the UBI though the Architect and no undertaking shall relieve the contractor from the responsibility of the contractor form active superintendence of the work during its progress.

16.0 QUALITY OF MATERIALS, WORKMANSHIP & TEST

i) All materials and workmanship shall be best of the respective kinds described in the contract and in accordance with the Architect/Consultant's instruction and shall be subject from time to time to such test as the Architect/Consultant may direct at the place of manufacture of fabrication or on the site or in an approved testing laboratory. The contractor shall provide such assistance, instruments, machinery, labor and materials as are normally required for examining, measuring, sampling and testing any material or part of work before incorporation in the work for testing a may be selected and required by the Architect/Consultant.

ii) Samples

All samples of adequate numbers, size, shades & pattern as per specifications shall be supplied by the contractor without any extra charges. If certain items proposed to be used are of such nature that samples cannot be presented or prepared at the site detailed literature/test certificate of the same shall be provided to the satisfaction of the Architect/Consultant. Before submitting the sample/literature the contractor shall satisfy himself that the material/equipment for which he is submitting the sample/literature meet with the requirement of tender specification. Only when the samples are approved in writing by the Architect/Consultant the contractor shall proceed with the procurement and installation of the particular material/equipment. The approved samples shall be signed by the Architect/Consultant for the identification and shall be kept on record at site office until the completion of the work for inspection/comparison at any time. The Architect/Consultant shall take responsibility time to approve the sample. Any delay that might occur in approving the samples for reasons of its not meeting the specifications or other discrepancies, inadequacy, delay in furnishing samples of best qualities from various manufactures and such other aspects causing delay on the approval of the material/equipment etc. shall be to the account of the contractor.

iii) Costs of Test

The cost of making any test shall be borne by the contractor if such test is intended by or provided for in the specifications or BOQ.

iv) Cost of test not provided for

If any test is ordered by the Architect/Consultant which is either

a) If so intended by or provide for or (in the cases above mentioned) is not so particularized, or though so intended or provided for but ordered by the Architect/Consultant to be carried out by an independent person at any place other than the site of the place of manufacture or fabrication of the materials tested or any Government approved laboratory, then the cost of such test shall be borne by the contractor.

17.0 OBTAINING INFORMATION RELATED TO EXECUTION OF WORK:

No claim by the contractor for additional payment shall be entertained which is consequent upon failure on his part to obtain correct information as to any matter affecting the execution of the work or any misunderstanding or the obtaining incorrect information or the failure to obtain correct information relieve him from any risks or from the entire responsibility for the fulfillment of contract.

18.0 CONTRACTOR'S SUPERINTENDENCE

The contractor shall give necessary personal superintendence during the execution of the works and as long, thereafter, as the Architect/Consultant may consider necessary until the expiry of the defect's liability period, hereto.

19.0 QUANTITIES:

i) The bill of quantities (BOQ) unless or otherwise shall be deemed to have been prepared in accordance with the Indian Standard method of Measurements and quantities. The rate quoted shall remain valid for variation of quantity against individual item to any extent.

20.0 WORKS TO BE MEASURED

The Architect/Consultant may from time to time intimate to the contractor that he requires the work to be measured and the contractor shall forthwith attend or send a qualified representative to assist the Architect in taking such measurements and calculations and to furnish all particulars or to give all assistance required by any of them. Such measurements shall be taken in accordance with the mode of Measurements detailed in the specifications. The representative of the Architect/Consultant shall take the joint measurements with the contractor's representative and the measurements shall be entered in the measurement book. The contractor or his authorized representative shall sign all the pages of the measurement book in which the measurements have been recorded in token of his acceptance. All the corrections shall be duly attested by both representatives. No over writings shall be made in the measurement book. Should the contractor no attend or neglect or omit to depute his representative to take measurements then the measurements recorded by the representative of the

Architect/Consultant shall be final. All authorized extra work, omissions and all variations made shall be included in such measurement,

21.0 VARIATIONS

No alteration, omission or variation ordered in writing by the Architect/Consultant shall vitiate the contract. In case the UBI/Architect/Consultant thinks proper at any time during the progress of works to make any alteration in, or additions to or omissions from the works or any alteration in the kind or quality of the materials to be used therein, the Architect/Consultant shall give notice thereof in writing to the contractor or shall confirm in writing within seven days of giving such oral instructions, the contractor shall alter to, add to, or omit from as the case may be in accordance with such notice, but the contractor shall not do any work extra to or make any alterations or additions to or omissions from the works or any deviation from any of the provisions of the contract, stipulations, specifications or contract drawings without previous consent in writing of the Architect/Consultant and the value of such extras, alternations, additions or omissions shall in all cases be determined by the Architect/Consultant and the same shall be added to or deducted from the contract value, as the case may be.

22.0 VALUATION OF VARIATIONS:

- a) No claim for an extra shall be allowed unless it shall have been executed under the authority of the Architect/Consultant with the concurrence of the UBI s herein mentioned. Any such extra is herein referred to as authorized extra and shall be made in accordance with the following provisions.
 - i) The net rates or prices in the contract shall be determine in the valuation of the extra work where such extra work is of similar character and executed under similar conditions as the work priced herein.
 - ii) Rates for all items, wherever possible should be derived out of the rates given in the priced BOQ.
- b) The net price of the original tender shall determine the value of the items omitted, provided if omissions do not vary the conditions under which any remaining items of works are carried out, otherwise the prices for the same shall be valued under sub-clause (c) hereunder.
- c) Where the extra works are not of similar character and/or executed under similar conditions are aforesaid or where the omissions vary the conditions under which any remaining items or works are carried out, then the contractor shall within 7 days of the receipt of the letter of acceptance inform the Architect/Consultant of the rate which he intends to charge for such items of work, duly supported by analysis of the rate or rates claimed and the Architect/Consultant shall fix such rate or prices as in the circumstances in his opinion are reasonable and proper based on the market rate.
- d) Where extra work cannot be properly measured or valued the contractor shall be allowed day work prices at the net rates Union in the tender of the BOQ or, if not, so Union then in accordance with the local day work rates and wedges for the district; provided that in either case, vouchers specifying the daily time (and if required by the Architect/Consultant) the workman's name and materials employed be delivered for verifications to the Architect/Consultant at or before the end of the week following that in which the work has been executed.
- e) It is further clarified that for all such authorized extra items where rates cannot be derived from the tender, the Contractor shall submit rates duly supported by rate analysis worked on the "market rate basis" for material, labor, hire/running charges of equipment's and wastage etc. plus 15% toward establishment charges, contractor's overheads and profits. Such items shall not be eligible for escalation.

23.0 FINAL MEASUREMENTS:

The measurements and the valuation in respect of the contract shall be completed within six months of the virtual completion of the work.

24.0 VIRTUAL COMPLETION CERTIFICATE (VCC)

On successful completion of the entire works covered by the contract to the full satisfaction of the UBI, the contractor shall ensure that the following works has been completed to the satisfaction of the UBI.

- a) Clear the site of all scaffolding, wiring, pipes, surplus materials, contractor's labor, equipment and machinery.
- b) Demolish, dismantle and remove the contractor's site office, temporary works, structure including labor sheds/camps and construction of other items and things whatsoever brought upon or erected at the site or any land allotted to the contractor by the UBI and not incorporated in the permanent works.

- c) Remove all rubbish, debris etc. from the site and the land allotted to the contractor by the UBI and shall clear, level and dress, compact the site as required by the UBI.
- d) Shall put the UBI in undisputed custody and possession of the site and all land allotted by the UBI.
- e) The contractor shall hand over the work in a peaceful manner to the UBI.
- f) All defects/imperfection have been attended and rectified as pointed out by the UBI to the full satisfaction of the UBI.

Upon the satisfactory fulfillment by the contractor as Union above, the contractor shall be entitled to apply to the Architect/Consultant is satisfied of the completion of the work. Relative to which the completion certificate has been sought, the Architect/Consultant shall within fourteen (14) days of the receipt of the applicant for virtual completion certificate, issue a VCC in respect of the work for which the VCC has been applied.

This issuance of a VCC shall be without prejudice to the UBI's rights and contractors liabilities under the contract including the contractor's liability for defect liability period nor shall the issuance of VCC in respect of the works or work at any site be construed as a waiver of any right or claim of the UBI against the contractor in respect of works or works at the site and in respect of which the VCC has been issued.

25.0 WORK BY OTHER AGENCIES:

The UBI/the Architect/Consultant reserve the rights to use premises and any portion of the site for execution of any work not included in the scope of this contract which it may desire to have carried out by other persons simultaneously and the contractor shall not only allow but also extend reasonable facilities for the execution of such work. The contractor however shall not be required to provide any plant or material for the execution of such work except by special arrangement with the UBI. Such work shall be carried out in such manner as not to impede the progress of the works included in the contract.

26.0 INSURANCE OF WORKS:

Without limiting his obligations and responsibilities under the contract the contractor shall insure in the joint names of the UBI and the contractor against all loss or damages from whatever cause arising other than the excepted risks, for which he is responsible under the terms of contract and in such a manner that the UBI and contractor are covered for the period stipulated in clause 28 of GCC and are also covered during the period of maintenance for loss or damage arising from a cause, occurring prior to the commencement of the period of maintenance and for any loss or damage occasioned by the contractor in the course of any operations carried out by him for the purpose of complying with his obligations under clause.

- a) The works for the time being executed to the estimated current contract value thereof, or such additional sum as may be specified together with the materials for incorporation in the works at their replacement value.
- b) The constructional plant and other things brought on to the site by the contractor to the replacement value of such constructional plant and other things.
- c) Such insurance shall be affected with an insurer and in terms approved by the UBI which approval shall not be unreasonably withheld and the contractor shall whenever required produce to the Architect/Consultant the policy of insurance and the receipts for payments of the current premiums.

26.1 DAMAGE TO PERSONS AND PROPERTY

The contractor shall, except if and so far as the contract provides otherwise indemnify the UBI against all losses and claims in respect of injuries or damages to any person or material or physical damage to any property whatsoever which may arise out of or in consequence of the execution and maintenance of the works and against all claims proceedings, damages, costs, charges and expenses whatsoever in respect of or in relation thereto except any compensation of damages for or with respect to:

- a) The permanent use or occupation of land by or any part thereof.
- b) The right of UBI to execute the works or any part thereof, over, under, in or through any lands.
- c) Injuries or damages to persons or properties which are unavoidable result of the execution or maintenance of the works in accordance with the contract.
- d) Injuries or damages to persons or properties resulting from any act or neglect of the UBI, their agents, employees or other contractors not being employed by the contractor or for or in respect of any claim, proceedings damages, costs, charges and expenses in respect thereof or in relation thereto or where the injury or damage was contributed to by the contractor, his servants or agents. Such part of the compensation as may be just and equitable having regard to the extent of the

responsibility of the UBI, their employees, or agents or other employees, or agents or other contractors for the damage or injury.

26.2 CONTRACTOR TO INDEMNIFY UBI

The contractor shall indemnify the UBI against all claims, proceedings, damages, costs, charges and expenses in respect of the matters referred to in the provision of this sub-clause 26.2.

26.3 CONTRACTOR'S SUPERINTENDENCE

The contractor shall fully indemnify and keep indemnified the UBI against any action, claim or proceeding relating to infringement or use of any patent or design or any alleged patent or design rights and shall pay any royalties which may be payable in respect of any article or part thereof included in the contract. In the event of any claim made under or action brought against UBI in respect of such matters as aforesaid the contractor shall be immediately notified thereof and the contractor shall be at liberty, at his own expenses to settle any dispute or to conduct any litigation that may arise there from, provided that the contractor shall not be liable to indemnify the UBI if the infringement of the patent or design or any alleged patent or design right is the direct result of an order passed by the Architect/Consultant in this behalf.

26.4 THIRD PARTY INSURANCE

26.4.1 Before commencing the execution of the work the contractor but without limiting obligations and responsibilities under clause **26.0** of GCC shall insure against his liability for any material or physical damage, loss, or injury which may occur to any property including that of UBI, or to any person, including any employee of the UBI, by or arising out of the execution of the works or in the carrying out of the contract, otherwise than due to the matters referred to in the provision to clause **26.0** thereof.

26.4.2 MINIMUM AMOUNT OF THIRD-PARTY INSURANCE

Such insurance shall be effected with an insurer and in terms approved by the UBI which approval shall not be reasonably withheld and for at least the amount Union below. The contractor shall, whenever required produce to the Architect/Consultant the policy or policies of insurance cover and receipts for payment of the current premiums.

The minimum insurance cover for physical property, injury and death is Rs. 2.0 lacs per occurrence with the number of occurrences limited to four. After each occurrence contractor will pay additional premium necessary to make insurance valid for four occurrences always.

26.5 ACCIDENT OR INJURY TO WORKMAN:

26.5.1 The UBI shall not be liable for or in respect of any damages or compensation payable at law in respect or in consequence of any accident or injury to any workman or other person in the employment of the contractor or any sub-contractor, save and except an accident or injury resulting from any act or default of the UBI or their agents or employees. The contractor shall fully indemnify and keep indemnified the UBI against all such damages and compensations, save and except as aforesaid and against all claim's proceedings, costs, charges and expenses whatsoever in respect thereof or in relation thereto.

26.5.2 INSURANCE AGAINST ACCIDENTS ETC. TO WORKMEN:

The contractor shall insure against such liability with an insurer approved by the UBI during the whole of the time that any person is employed by him on the works and shall, when required, produce to the Architect/Consultant such policy of insurance and receipt for payments of the current premium. Provide always that, in respect of any persons employed by any sub-contractor, the contractor's obligation to insure as aforesaid under this sub-clause shall be satisfied if the sub-contractor shall have insured against the liability in respect of such persons in such manner that UBI is indemnified under the policy but the contractor shall require such sub-contractor to produce to the Architect/Consultant when such policy of insurance and the receipt for the payment of the current premium.

26.5.3 REMEDY ON CONTRACTOR'S FAILURE TO INSURE:

If the contractor fails to effect and keep in force the insurance to above referred to above or any other insurance which he may be required to effect under the terms of contract, then and in any such case the UBI may effect and keep in force any such insurance and pay such premium or premiums as may be necessary for that purpose and from time to time deduct the amount so paid by the UBI as aforesaid from any amount due or which may become due to the contractor, or recover the same as debt from the contractor.

26.5.4 Without prejudice to the other rights of the UBI against the contractor, in respect of such default, the Bank shall be entitled to deduct from any sums payable to the contractor the amount of any damages, costs, charges and other expenses paid by the UBI and which are payable by the contractor under this clause. The contractor shall upon settlement by the insurer of any claim made against the insurer pursuant to a policy taken under this clause, proceed with due diligence to rebuild or repair the works destroyed or damaged. In this event all the monies received from the insurer in respect of such

damage shall be paid to the contractor and the contractor shall not be entitled to any further payment in respect of the expenditure incurred for rebuilding or repairing of the materials or good destroyed or damaged.

27.0 COMMENCEMENT OF WORKS:

The date of commencement of the work will be reckoned as the date of handing over site or fifteen days from the date of issue of letter of acceptance of the tender by the UBI whichever is later.

28.0 TIME OF COMPLETION:

Time is essence of the contract and shall be strictly observed by the contractor. The entire work shall be completed within as specified in the NIT from the date of commencement. If required in the contract or as directed by the Architect/Consultant, the contractor shall complete certain portions of work before completion of the entire work. However, the completion date shall be reckoned as the date by which the whole work is completed as per the terms of the contract.

29.0 EXTENSION OF TIME:

If, in the opinion of the Architect/Consultant, the work be delayed for reasons beyond the control of the contractor, the Architect/Consultant may submit a recommendation to the UBI to grant a fair and reasonable extension of time for completion of work as per the terms for contract. If the contractor needs and extension of the time for completion of the work or if the completion of work is likely to be delayed for any reasons beyond the due date of completion as stipulated in the contract, the contractor shall apply to the UBI through the Architect/Consultant in writing at least 30 days before the expiry of the scheduled time and while applying for extension of time he shall furnish the reasons in detail and his justification if any, for the delays. The Architect/Consultant shall submit their recommendations to the UBI in the prescribed format for granting extension of time. While granting extension of time the contractor shall be informed the period extended times, which will quality for levy of liquidated damages. For the balance period in excess of original stipulated period and duly sanctioned extension of time by the UBI. The provision of liquidated damages as Union under clause 9 GCC shall become applicable. Further the correct shall remain in force even for the period beyond the due date of completion irrespective whether the extension is granted or not.

30.0 RATE OF PROGRESS:

Whole of the materials, plant and labor to be provided by the contractor and the mode, manner and speed of execution and maintenance of the works to be of a kind and conducted in a manner to the satisfaction of the Architect/Consultant should the rate of progress of the work or any part thereof be at any time be in the opinion of the Architect/Consultant too slow to ensure the completion the whole of the work by the prescribed time or extended time for completion the Architect/Consultant shall thereupon take such steps as considered necessary by the Architect/Consultant to expedite progress so as to complete the works by the prescribed time extended time. Such communications from the Architect/Consultant neither shall relieve the contractor from fulfilling obligations under the contract nor will he be entitled to raise any claims arising out of such directions.

31.0 WORK DURING NIGHTS AND HOLIDAYS:

Subject to any provision to the contrary contained in the contract no permanent work shall save as herein provided be carried on during the night or on holidays without the permission in writing of the Architect/Consultant, save when the work is unavoidable or absolutely necessary for the saving of life or property or for the safety of the work in which case the contractor shall immediately advise the Architect/Consultant. However, the provisions of the clause shall not be applicable in the case of any work which becomes essential to carry by rotary or double shifts in order to achieve the progress and quality of the part of the work being technically required/continued with the prior approval of the Architect/Consultant at no extra cost to the UBI.

All work at night after obtaining approval from competent authorities shall be carried out without unreasonable noise and disturbance.

32.0 NO COMPENSATION FOR RESTRICTIONS OF WORK:

If at any time after acceptance of the tender UBI shall deduct to abandon or reduce the scope of work for any reason whatsoever and hence not required the whole or any part of the work to be carried out, the Architect/Consultant shall give notice in writing to that effect to the contractor and the contractor shall act accordingly. In the matter the contractor shall have no claim to any payment of compensation or otherwise whatsoever on account of any profit or advantage which he might have derived from the execution of the work fully but which he did not derive in consequences of the foreclosure of the whole or part of the work.

Provided that the contractor shall be paid the charges on the cartage only of materials actually and bonafide brought to the site of the work by the contractor and rendered surplus as a result of the abandonment, curtailment of the work or any position thereof and taken back by the contractor, provided however that the Architect/Consultant shall have in such cases the

opinion of taking over all or any such material at their purchase price or at local current rate whichever is less. "In case such stores having been issued from UBI stores and returned by the contractor to stores, credits shall be given to him at the less rate not exceeding those at which were originally issued to the contractor after taking into consideration and deduction for claims on account of any deterioration or damage while in the custody of the contractor and in this respect the decision of the Architect/Consultant shall be final.

33.0 SUSPENSION OF WORK:

- i) The contractor shall, on receipt of the order in writing of the Architect/Consultant (whose decision shall be final and binding on the contractor) suspended the progress of work or any part thereof for such time and in such manner as the Architect/Consultant may consider necessary so as not to cause any damage or injury to the work already done or endanger the safety thereof for any of the following reasons:
 - a) On account any default on the part of the contractor, or
 - b) For proper execution of the works or part thereof for reasons other than the default the contractor or
 - c) The contractor shall during such suspension, properly protect and secure the works to the extent necessary and carry out the instructions given in that behalf by the Architect/Consultant.
- ii) If the suspension is ordered for reasons (b) and (c) in sub-para (i) above: The contractor shall be entitled to an extension of time equal to the period of every such suspension. No compensation whatsoever shall be paid on this account.

34.0 ACTION WHEN THE WHOLE SECURITY DEPOSIT IS FORFEITED

In any case in which under any clause or clauses of this contract, the contractor shall have rendered himself liable to pay compensation amounting to the whole of his security deposit the Architect/Consultant shall have the power to adopt any of the following course as they may deem best suited to the interest of the UBI.

- a) To rescind the contract (of which rescission notice in writing to the contractor by the Architect/Consultant shall be conclusive evidence) and in which case the security deposit of the contractor shall be forfeited and be absolutely at the disposal of UBI.
- b) To employ labor paid by the UBI and to supply materials to carry out the work, or any part of the work, debiting the contractor with the cost of the labor and materials (the cost of such labor and materials as worked out by the Architect/Consultant shall be final and conclusive against the contractor.) and crediting him with the value of the work done, in all respects in the same manner and at the same rates as if it had been carried out by the contractor under the terms of this contract, the certificate of the Architect/Consultant as to the value of work done shall be final and conclusive against the contractor.
- c) To measure up the work of the contractor, and to take such part thereof as shall be unexecuted, out of his hands, and to give it to another contractor to complete in which case any expenses which may be incurred in excess of the sum which would have been paid to the original contractor, if the whole work had been executed by him (of the amount of which excess the certificates in writing of the Architect/Consultant shall be final and conclusive) shall be borne by original contractor and may be deducted from any money due to him by the UBI under the contract or otherwise, or from his security deposit or the proceeds of sale thereof, or sufficient part thereof.

In the event of any of above courses being adopted by the UBI the contractor shall have no claim for compensation for any loss sustained by him by reasons of his having purchased or procured any material or entered into any engagements or make any advances on account of, or with a view to the execution of the work or the performance of the contract and in case the contract shall rescind under the provision aforesaid, the contractor shall not be entitled to recover or to be paid any sum or any work thereto for actually performed under this contract, unless, and until the Architect/Consultant will have certified in writing the performance of such work and the value payable in respect thereof, and he shall only be entitled to be paid the value so certified.

35.0 OWNER'S RIGHT TO TERMINATE THE CONTRACT:

If the contractor being an individual or a firm commit any 'Act of Insolvency' or shall be adjusted an Insolvent or being an incorporated company shall have an order for compulsory winding up voluntarily or subject to the supervision of Govt. and of the Official Assignee of the liquidator in such acts of insolvency or winding up shall be unable within seven days after notice to

him to do so, to show to the reasonable satisfaction of the Architect/Consultant that he is able to carry out and fulfill the contract and to give security therefore if so required by the Architect/Consultant.

Or if the contractor (whether an individual firm or incorporated company) shall suffer execution to be issued or shall suffer any payment under this contract to be attached by or on behalf of any of the creditors of the contractor. Or shall assign or sublet this contract without the consent in writing of the UBI through the Architect/Consultant or shall charge or encumber this contract or any payment due to which may become due to the contractor there under:

- a) has abandoned the contract; or
- b) has failed to commence the works, or has without any lawful excuse under these conditions suspended the progress of the works for 14 days after receiving from the UBI through the Architect/Consultant written notice to proceed, or
- c) has failed to proceed with the works with such diligence and failed to make such due progress as would enable the works to be completed within the time agreed upon, or has failed to remove the materials from the site or to pull down and replace work within seven days after written notice from the UBI through the Architect/Consultant that the said materials were condemned and rejected by the Architect/Consultant under these conditions; or has neglected or failed persistently to observe and perform all or any of the acts, matters or things by this contract to be observed and performed by the contractor for seven days after written notice shall have been given to the contractor to observe or perform the same or has to the detriment of good workmanship or in defiance to the UBI's or the Architect/Consultant's instructions to the contrary subject any part of the contract. Then and in any of said cases the UBI and or the Architect/Consultant, may not withstanding any previous waiver, after giving seven days' notice in writing to the contractor, determine the contract, but without thereby affecting the power the UBI or the Architect/Consultant or the obligation and liabilities of the contractor the whole of which shall continue in force as fully as if the contract had not been so determined and as if the works subsequently had been executed by or on behalf of the contractor. And further the UBI through the Architect/Consultant their agents or employees may enter upon and take possession of the work and all plants, tools, scaffoldings, materials, sheds, machineries lying upon the premises or on the adjoining lands or roads use the same by means of their own employees or workmen in carrying on and completing the work or by engaging any other contractors or persons to complete the work and the contractor shall not in any way interrupt or do any act, matter or thing to prevent or hinder such other contractor or other persons employed for completing and finishing or using the materials and plant for the works.

When the works shall be completed as soon thereafter as convenient the UBI or the Architect/Consultant shall give a notice in writing to the contractor to remove his surplus materials and plants and should the contractor fail to do so within 14 days after receipt thereof by him the UBI sell the same by public auction. The contractor shall have no right to question any of the act of the UBI incidental to the sale of the materials etc.

36.0 CERTIFICATE OF PAYMENT:

The contractor shall be entitled under the certificates to be issued by the Architect/Consultant to the contractor within 10 working days from the date of receipt of certificate to the payment from UBI from time to time. The UBI shall recover the statutory recoveries other dues including the retention amount from the certificates of payments.

They shall provide always that the issue of any certificate by the Architect/Consultant during the progress of works or completion shall not have effect as certificate of satisfaction or relieve the contractor from his liability under clause.

The Architect/Consultant shall have power to withhold the certificate if the work or any part thereof is not carried out to their satisfaction.

The Architect/Consultant may by any certificate make any corrections required in previous certificate.

The UBI shall modify the certificate of payments as issued by the Architect/Consultant from time to time while making the payment. The contractor shall submit interim bills only after taking actual measurements and properly recorded in the M books.

The contractor shall not submit interim bills when the approximate value of work done by him is less than Rs 6 lacs and the minimum interval between two such bills shall be one month.

The final bill may be submitted by the contractor within a period of one month from the date of virtual completion and the Architect/Consultant shall issue the certificate of payment within a period of two months. The UBI shall pay the amount within a period of three months from the date of issue of certificate provided there is no dispute in respect of rates and quantities etc.

The contractor shall submit the interim bills in the prescribed format with all details.

37.0 SETTLEMENT OF DISPUTES AND ARBITRATION:

Except where otherwise provided in the contract all questions and disputes relating to the meaning of the specifications, design, drawings and instructions herein before mentioned and as to the quality of workmanship or materials used on the work or as to any other question, claim, right, matter or thing whatsoever in any way arising out of or relating to the contract, designs, drawings, specifications, estimates, instruction, orders or these conditions or otherwise concerning the work or the execution or failure to execute the same whether arising during the progress of the work or after the cancellation, termination, completion or abandonment thereof shall be dealt with as mentioned hereinafter.

i) If the contractor consider that he is entitled to any extra payment or compensation in respect of the works over and above the amounts admitted as payable by the Architect or in case the contractor wants to dispute the validity of any deductions or recoveries made or proposed to be made from the contract or raise any dispute, the contractors shall forthwith give notice in writing of his claim, or dispute to **REGIONAL OFFICE, VADODARA** and endorse a copy of the same to the Architect, within 30 days from the date of disallowance thereof or the date of deduction or recovery. The said notice shall give full particulars of the claim, grounds on which it is based and detailed calculations of the amount claimed and the contractor shall not be entitled to raise any claim nor shall the Bank be in any way liable in respect of any claim by the contractor unless notice of such claim shall have been given by the contractor to the **REGIONAL OFFICE, UBI VADODARA**. in the manner and within the time as aforesaid. The contractor shall be deemed to have waived and extinguished all his rights in respect of any claim not notified to the Chief Manager (P&E) in writing in the manner and within the time aforesaid.

ii) The Chief Manager (P&E) shall give his decision in writing on the claims notified by the contractor. The contractor may within 30 days of the receipt of the decision of the Chief Manager (P&E) submit his claims to the conciliating authority namely the for conciliation along with all detail and copies of correspondence exchanged between him and the Deputy General Manager.

iii) If the conciliation proceedings are terminated without settlement of the disputes, the contractors shall, within a period of 30 days of termination thereof shall give a notice to the concerned CHIEF GENERAL MANAGER of the Bank for appointment of an arbitrator to adjudicate the notified claims failing which the claims of the contractor shall be deemed to have been considered absolutely barred and waived.

iv) Except where the decision has become final, binding and conclusive in terms of the contract, all disputes or differences arising out of the notified claims of the contractor as aforesaid and all claims of the Bank shall be referred for adjudication through arbitration by the Sole Arbitrator appointed by the CHIEF GENERAL MANAGER. It will so be no objection to any such appointment that the Arbitrator so appointed is a Bank Officer and that he had to deal with the matters to which the contract relates in the course of his duties as Bank Officer. If the arbitrator so appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed in the manner aforesaid by the said Chief General Manager. Such person shall be entitled to proceed with the reference from the stage at which it was left by his predecessor.

It is a term of this contract that the party invoking arbitration shall give a list of disputes with amounts claimed in respect of each dispute along with the notice for appointment of arbitrator.

It is also a term of this contract that no person other than a person appointed by such Chief General Manager as aforesaid should act as arbitrator.

The conciliation and arbitration shall be conducted in accordance with the provisions of the Arbitration & Conciliation Act 1996 or any statutory modification or reenactment thereof and the rules made there under.

It is also a term of this contract that if any fees are payable to the arbitrator, these shall be paid equally by both the parties. However, no fees will be payable to the arbitrator if he is a Bank Officer.

It is also a term of this contract that the arbitrator shall be deemed to have entered on the reference on the date he issues notice to both the parties calling them to submit their Union of claims and counter Union of claims. The venue of the arbitration shall be such place as may be fixed by the arbitrator in his sole discretion. The fees, if any, of the arbitrator shall, if required to be paid before the award is made and published, be paid half and half by each of parties. The cost of the reference and of the award (including the fees, if any, of the arbitrator) shall be in the discretion of the arbitrator who may direct to any by whom and in what manner, such costs or any part thereof, shall be paid and fix or settle the amount of costs to be so paid.

38.0 WATER SUPPLY

The contractor shall make his own arrangement for water required for the work and nothing extra will be paid for the same. This will be subjected to the following conditions:

- i) That the water used by the contractor shall be fit for construction purposes to the satisfaction of the Architect/Consultant.
- ii) The contractor shall make alternative arrangement for the supply of water if the arrangement made by the contractor for procurement of water in the opinion the Architect/Consultant is unsatisfactory.

38.1 The contractor shall construct temporary well/tube well in UBI land for taking water for construction purpose only after obtaining permission in writing for the UBI. The contractor has to make his own arrangements for drawing and distributing the water at his own cost. He has to make necessary arrangements, to avoid any accidents or damage caused due to construction and subsequent maintenance of the well. He has to obtain necessary approvals from the local authorities, if required, at his own cost. He shall restore the ground to its original condition after wells are dismantled on completion of the work or hand over the well to the UBI without any compensation as directed by the Architect/Consultant.

39.0 POWER SUPPLY:

The contractor shall make his own arrangement for power and supply/distribution system for driving plant or machinery for the work and for lighting purpose at his own cost. The cost of running and maintenance of the plants are too included in his tender prices. He shall pay all fees and charges required for the power supply and include the same in his tendered rates and hold the owner free from all such costs. He has to obtain necessary approvals from the appropriate authorities, if required.

40.0 TREASURE TROVE ETC.:

Any treasure trove, coin or object antique which may be found on the site shall be the property of the UBI and shall be handed over to the bank immediately.

41.0 METHOD OF MEASUREMENTS:

Unless otherwise mentioned in the schedule of quantities or in mode of measurement or elsewhere in these documents the measurement will be on the net quantities or work produced in accordance with up to date as per rules laid down by the Bureau of Indian Standards. In the event any dispute/disagreement the decision of the Architect/Consultant shall be final and binding on the contractor.

42.0 MAINTENANCE OF REGISTERS:

The contractor shall maintain the registers as directed/instructed by the Bank/Architects as per the approved Performa at site of work and should produce the same for inspection of the UBI/the Architect/Consultant whenever desired by them. The contractor shall also maintain the records/registers as required by the local authorities/Govt. from time to time.

- (1) Register for secured advance
- (2) Register for Hindrance to work
- (3) Register for Running Account Bill
- (4) Register for Labor

43.0 FORCE MAJEURE:

43.1 Neither contractor nor UBI shall be considered in default in performance of their obligations if such performance is prevented or delayed by events such as but not to war, hostilities revolution, riots, civil commotion, strikes, lockout, conflagrations, epidemics, accidents, fire, storm, floods, droughts, earthquakes or ordinances or any act of god or for any other cause beyond the reasonable

control of the party affected or prevented or delayed. However, a notice is required to be given within 30 days from the happening of the event with complete details to the other party to the contract, if it is not possible to serve a notice, within the shortest possible period without delay.

43.2 As soon as the clause of force majeure has been removed the party whose ability to perform its obligations has been affected, shall notify the other of such cessation and the actual delay incurred in such affected activity adducing necessary evidence in support thereof.

43.3 From the date of occurrence of a case of force majeure obligations of the party affected shall be suspended during the continuance of any inability so caused. With the cause it and inability resulting their form having been removed, the agreed time of completion of the respective obligations under this agreement shall stand extended by a period equal to the period of delay occasioned by such events.

43.4 Should one or both parties be prevented from fulfilling the contractual obligations by a Union of force major lasting to a period of 6 months or more the two parties shall each other to decide Regarding the future execution of this agreement?

44.0 LOCAL LAWS, ACTS, REGULATIONS:

The contractor shall strictly adhere to all prevailing labor laws inclusive of contract labor (regulation and abolition act of 1970) and other safety regulation. The contractor shall comply with the provision of all labor legislation including the latest requirements of all the Acts, Laws, any other regulations that are applicable to the execution of the project.

- i) Minimum Wages Act 1948 (Amended)
- ii) Payment of Wages Act 1936 (Amended)
- iii) Workmen's Compensation Act 1923 (Amended)
- iv) Contract labor regulation and abolition act 1970 and central rules 1971 (Amended)
- v) Apprentice act 1961 (Amended)
- vi) Industrial employment (standing order) Act 1946 (Amended)
- vii) Personal injuries (compensation insurance) act 1963 and any other modifications
- viii) Employees' provident fund and miscellaneous provisions Act 1952 and amendment thereof
- ix) Shop and establishment Act
- x) Any other act or enactment relating thereto and rules framed there under from time to time.

46.0 ACCIDENTS:

The contractor shall immediately on occurrence of any accident at or about the site or in connection with in execution of the work report such accident to the Architect/Consultant. The contractor shall also such report immediately to the competent authority wherever such report is required to be lodged by the law and take appropriate actions thereof.

47.0 REMOVAL OF IMPROPER WORK:

The Bank / Architect shall during the progress of the work have power to order in writing form time to time the removal from the work within such reasonable time to time as any be specified in the order of any materials which in the opinion of the Bank / Architects are not in accordance with specification or instructions, the substitution or proper re-execution of any work executed with materials or workmanship not in accordance with the drawings and specifications or instruction. In case the contractor refuses to comply with the order the Bank shall have the power to employ and pay other agencies to carry out the work and all expenses consequent thereon or incidental thereof as certified by the Bank /Architects shall be borne by the contractor or may be deducted from any money due to or that may become due to the contractor. No certificate, which may be given by the Architects, shall relieve the contractor from his liability in respect of unsound work or bad materials. The decision of the Banks in this regard shall be final and binding on the contractor.

48.0 DISMISSAL OF WORKMEN:

The contractor shall on the request of the Bank / Architect immediately dismiss from works any person employed thereon by him. Who may in opinion of the Bank / Architect is unsuitable or incompetent or who may misconduct? Such discharge shall not be the basis of any claim for compensation or damages against the Bank or any of their chief officer or employee.

49.0 CONTRACTOR'S EMPLOYEES:

The contractor shall employ technically qualified and competent supervisors for the work shall be available (by turn) throughout the working hours to receive and comply with instructions of the Bank /Architects. The contractor shall engage at least one experienced engineer as site in charge for execution of the work. The contractor shall employ in connection with the work persons having the appropriate skill or ability to perform their job efficiently. The contractor shall employ local laborers on the work as far as possible. No laborer below the age of sixteen years and who is not an Indian shall be employed on the work. Any laborer supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order on control of the Bank or his representative shall be a person employed by the contractor. The contractor shall comply with the provisions of all labor legislation including the requirements of

- (a) The payment of wages act.
- (b) Bank 's liability act.
- (c) Workmen's compensation act.
- (d) Contract labor (regulation & abolition) act, 1970 and central rules 1971.
- (e) Apprentices act. 1961.
- (f) Any other act or enactment relating thereto and rules framed hereunder from time to time.

The contractor shall keep the Bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the Bank in connection with any claim that may be made by any workmen. The contractor shall comply at his own cost with the order of requirement of any health officer of the State or any local authority or the Bank regarding the maintenance of proper environmental sanitation of the area where the contractor's laborers are housed or accommodated, for the prevention of small pox, cholera, plague, typhoid, malaria and other contagious diseases. The contractor shall provide, maintain and keep in good sanitary condition adequate sanitary accommodation and provide facilities for pure drinking water at all times for the use of men engaged on the works and shall remove and clear away the same on completion of the works. Adequate precautions shall be taken by the contractor to prevent nuisance of any kind on the works. Adequate precautions shall be taken by the contractor to prevent nuisance of any kind on the works or the lands adjoining the same. The contractor shall arrange to provide first-aid treatment to the laborer's engaged on the works. He shall within 24 hours of the occurrence of any accident at or about the site or in connection with execution of the works, report such accident to the Bank and also to the competent authority where such report is required by law.

50.0 ASSIGNMENT:

The contractor shall execute the whole of the works included in the contract and the contractor shall not directly or indirectly transfer, assign or underwrite the contract or any part, share or interest therein nor, shall take a new partner, without written consent of the Bank and no subletting shall relieve the contractor from the full and entire responsibility of the contract or from active superintendence of the work during their progress.

51.0 CLEARING SITE ON COMPLETION:

On completion of the works the contractor shall clear away and remove from the site all construction plant, surplus material, rubbish and temporary works of every kind and leave the whole of the site and the works clean and in a workmanlike condition to the satisfaction of the Bank / Architects.

52.0 DEFECTS AFTER COMPLETION:

The contractor shall make good at his own cost and to the satisfaction of the Bank / Architects all defects, shrinkage, settlements or other faults which may appear within 12 months after completion of the work- In default the Bank may employ and pay other persons to amend and make good such damages, losses and expenses consequent thereon or incidental thereto shall be made good and borne by the contractor and such damages, loss and expenses shall be recoverable from him by the Bank or may be deducted by the Bank, in lieu of such amending and making good by the contractor, deduct from any money due to the contractor a sum equivalent to the cost of amending such work and in the event of the amount retained being insufficient, recover that balance from the contractor from the amount retained together with any expenses the Bank may have incurred in connection therewith.

53.0 CONCEALED WORK:

The contractor shall give due notice to the Bank / Architects whenever any work is to be buried in the earth, enclosed or in the bodies of walls or otherwise becoming inaccessible later on, in order that the work may be inspected and correct dimensions taken before such burial, in default whereof the same shall, at the opinion of the Bank / Architect be either opened up for measurement at the contractor's expenses or no payment may be made for such materials. Should any dispute or differences arise after the execution of any work as to measurements etc. or other matters which cannot be conveniently tested or checked the notes of the Bank / Architects shall be accepted as correct and binding on the contractor.

54.0 ESCALATION:

The rate quoted shall be firm throughout the tenure of the contract including extension of time, if any, granted and will not be subject to any fluctuation due to increase in cost or materials, labor, sales tax, octroi, etc. (EXCLUDING GST).

55.0 SIGNING OF TENDER:

The tender shall contain the name residence and place of business of person or person making the tender and shall be signed by the contractor with his usual signature. Partnership firms shall furnish the full name of all partners in the tender. It should be signed in the partnership name by all partners or by duly authorized representative followed by corporation shall be signed by an authorized representative, and in power of Attorney in that behalf shall accompany the tender. A copy of constitution of the firm with names of all partners shall be furnished.

56.0 TRANSFER OF TENDER DOCUMENTS:

Transfer of tender documents purchased by one intending contractor to another is not permitted.

CONDITIONS OF THE CONTRACT

NOTE:

The requirements of these conditions shall be fulfilled by the Tenderer without extra charges, the item rates quoted shall be deemed to have taken these conditions into account.

3.1 If any additions and alterations are found necessary the Tenderer will have to do the same within the Tendered rates with the approval of the Bank.

3.2 The Contractor shall employ adequate labor to complete the work within the scheduled time and shall make his own arrangements for housing materials etc.

3.3 The Contractor shall have to make his own arrangements to house & food for his labor and staff, and for their services.

3.4 All Tendered rates shall include for the cost of materials, labor, supervision, tools, plant, transport, all taxes, contingencies duties, breakages, wastages, sundries, scaffolding etc., complete.

3.5 All instructions regarding the execution of works shall be received from the Bank only. Any other instructions issued directly to the contractor by anyone else shall not be binding on the Contractor.

3.6 The Bank, through the Consultants, shall have the power on omit or cancel; any item of work without assigning any reason whatsoever and no claim for compensation for damage will be entertained for such omissions and cancellations.

3.7 The Contractor shall maintain satisfactory progress of work as well as maintain a desired level of workmanship. If in the opinion of the Bank if the progress is unsatisfactory and/or the workmanship is unsatisfactory, the Bank shall take possession of the work with 7 days to that effect. The Bank shall then complete the entire work and rectify all the defects at the Contractors cost and consequences.

3.8 The case the Bank is not satisfied with the quality of materials used by the Contractors, Bank reserves the right to direct the Contractor to procure such supplies from the agencies suggested by the Bank and the Contractor is bound by this instruction for purchase of materials.

3.9 The Contractor is to be responsible for clearing any or all dirt, rubbish, and superfluous materials as they accumulate and to leave the premises in a clean and orderly condition on completion. No extra payment shall be made for doing this work.

3.10 Any work which is not approved by the Bank shall have to be removed within 24 hours from the time of order and shall have to be redone by the Contractor at his own cost and this cost will be borne by the Contractor.

3.11 No deviation whatsoever for any reason will be permitted. However, if any deviation becomes necessary, the same should be brought to the immediate notice of the Bank and written approval must be obtained for such deviation before proceeding with the execution of work.

3.12 The Bank has got the right to supply any materials required for the work and the cost of the materials so supplied will deducted from the bills of the successful Contractor.

3.13 The Contractor shall be responsible for the safe custody of the materials issued to him by the Bank till they are used for the work. He shall make his own arrangements for the safe custody and proper storage and preservation in sound conditions till the same are actually used in the work.

3.14 For any new item the rate will be fixed by the Bank as per prevailing fair market rate, labor and overheads which will be binding on the Contractor.

3.15 The Contractor shall have a competent supervisor on the site all the times.

3.16 In case the brand of materials mentioned in the Tender is not available in the market, the alternate materials to be used shall be approved by the Bank.

3.17 The Contractor should strictly adhere to the specifications and make of the materials.

3.18 Any clarification on the specifications or further details needed, the Contractor has to contact the Bank.

3.19 Contractor should ensure the safety of his staff / Technicians/ Labor working at the work site. He should provide all necessary safety equipment to his personnel working at the site.

3.20 Contractor should obtain necessary Group Insurance for his personnel working at the site to provide medical treatment / compensation etc. to any of his staff/worker in case of any accident. Bank is not bound to provide any assistance of any form in this matter.

ACCEPTANCE OF CONTRACTOR FOR LABOR LAWS

1. The successful Tenderer / Contractor shall carefully and diligently implement the provisions of the Contract Labor Act & Contract Labor Rules.
2. The Bank shall be entitled to deduct from the Contract Consideration, any such amount which the Bank has to pay in accordance with the Contract Labor (Regulation & Abolition) Act 1971 and Workmen's Compensation Act, in the event of the Bank have to disburse compensation / effect any payment under the Contract Labor Acts / Rules.
3. Please note that as per rule 81(1) of Contract Labor (R&A) Rules, 1971, it is mandatory on the part of the Contractor to display the notice containing the following details at prominent place at the work site.
 - (a) Rates of wages.
 - (b) Hours of work.
 - (c) Wage periods.
 - (d) Dates of payment of wages.
 - (e) Names & addresses of the Labor Inspectors having jurisdiction &
 - (f) Date of payment of unpaid wages. The notice containing the above details shall be displayed without fail at the work site.
4. The Contractor shall not engage any workmen for wages, less than the minimum wages prescribed under the notification issued by the Central Government.
5. The contractor should follow all labor laws/guidelines laid down by central /state government from time to time.

CERTIFICATE

I / WE HAVE READ, FULLY UNDERSTOOD THE ABOVE-MENTIONED REGULATIONS OF LABOR LAWS/GUIDELINES AND ACCEPT THE SAME IN TOTO. I ALSO UNDERTAKE TO FOLLOW ALL LABOR LAWS/GUIDELINES LAID DOWN BY CENTRAL /STATE GOVERNMENT FROM TIME TO TIME & INDEMNIFY THE BANK AUTHORITIES.

SIGNATURE OF THE CONTRACTOR
WITH SEAL & DATE

SAFETY CODES: GENERAL SAFETY CODES:

1. First aid appliances including adequate supply of sterilized dressing and cotton wool shall be kept in a readily accessible place.
 2. An injured shall be taken to a Public Hospital without loss of time, in cases where the injury necessitates hospitalization.
 3. Suitable and strong scaffolds should be provided for workman for all works that cannot safely be done from the ground.
 4. No portable single ladder shall be over 8meters in length. The width between the side rails shall not be less than 30 cm. clear. And the distance between two adjacent rungs shall not be more than 30 cm When a ladder is used an extra mazdoor shall be engaged for holding ladder.
 5. The excavated material shall not be placed within 1.5meters of the edge of the trench or half of the depth of trenches whichever is more. All trenches and excavation shall be provided with necessary fencing and lighting.
 6. Every opening in the floor of a building or in a working platform be provided with suitable means to prevent the fall of persons or materials by providing suitable fencing or railing whose minimum height shall be one meter.
 7. No floor, roof or other part of the structure shall be so overloaded with debris or materials as to render it unsafe.
 8. Workers employed on mixing & handling material such as asphalt, cement mortar or concrete & lime mortar shall be provided with protective footwear & rubber hand-gloves.
 9. Those engaged in welding work shall be provided with welder's protective eye-shields and gloves.
 10. (i) No paint containing lead or lead products shall be used except in the form of paste and readymade paint.
(ii) Suitable facemasks should be supplied for use by the workers when the paint applied in the form of spray or surface having lead paint dry rubbed and scrapped.
 11. Overalls shall be supplied by the contractor to the painters and the adequate facilities shall be provided to enable the working painters to wash during the periods of cessation of works.
 12. Hoisting machine and tackle used in the works, including their attachments, anchors and supports shall be in perfect condition.
- The ropes used in hoisting or lowering material or as a means of suspension shall be of durable quality and adequate strength free from defect.

FIRST AID

- (a) At every work place, there shall be maintained in readily accessible place first aid appliance including an adequate supply of sterilized dressing and sterilized cotton wool. The appliance shall be kept in good order and in large work place they shall be placed under the charge of a responsible person who shall be readily available during working hours.
- (b) At large work places, where hospital facilities are not available within easy distance of the works, first aid posts shall be established and be run by a trained compounder.
- (c) Where large work places are remote from regular hospitals, an indoor ward shall be provided with one bed for every 250 employees.
- (d) Where large work places are situated in cities, towns in their suburbs and no beds are considered necessary owing to the proximity of city or town hospital, suitable transport shall be provided to facilitate removal or urgent cases to the hospitals. At other work places some conveyance facilities such as a car, shall be kept readily available to take injured person or persons suddenly taken ill to the nearest hospital.

DRINKING WATER

- (a) In every work place, there shall be provided and maintained at suitable places easily accessible to labor sufficient supply of cold water fit for drinking.
- (b) Where drinking water is obtained from an intermittent public water supply, each work place shall be provided with storage where such drinking water shall be stored.
- (c) Every water supply of storage shall be at a distance of not less than 15m. from any latrines, drain or other source of pollution. Where water has to be drawn from an existing well which the proximity of latrine, drain or any other source of pollution, the well shall be properly chlorinated before water is drawn from it for drinking. All such wells shall be entirely closed in and be provided with a trap door, which shall be dust and waterproof.
- (d) A reliable pump shall be fitted to each covered well, the trap door shall be kept locked and opened only for cleaning or inspection which shall be done at least once a month.

PREAMBLE AND SPECIFICATIONS

The quantities given in this schedule of quantities are approximate and subject to variations without vitiating the contract.

Pricing:

The rate for each item of work shall, unless expressly stated otherwise, include the following (but not limited to the list given below) for the completion of works in all respects as per conditions of Contract, technical specifications, drawing etc.:

All taxes such as Octroi, Sales tax, Work Contract Tax, Royalties, Transportation, Freights, Packing and forwarding charges Insurance etc.,

All requirements and expenses for completion of work as per Rules and Regulations of Local Bodies, State Government and Central Government of India.

All materials, equipment's, accessories, consumable, controls and instruments, tools, tackles, plants, scaffolding/double scaffolding labor, maintenance, fixing, cleaning, making good hauling, hoisting etc.,

Waste on material and labor.

Loading, Unloading, handling/double handling, setting out protection from weather, temporary supports, platforms etc., and the maintenance, of the same, dismantling of temporary works, disposal of debris and all other labor necessary for the execution of works.

Testing the installation as often as necessary, Contractors to arrange for all special instruments and tools required for such testing.

Painting of all equipment, pipes, supports etc., as per color codes to be decided for various systems.

Apportion of costs for general facilities to be used by the Contractor's staff such as lifts, electricity, telephones etc. during execution if such facilities are provided by other contractors and who arrange for such facilities in the first instance.

Fees for testing the materials, equipment or overall installation by appropriate authorities.

Supervising Civil/ Masonry / Carpentry Works done by other agencies on behalf of the **Bank** for electrical contractor.

All requirements of specification and drawings. Description of work given in the schedule of quantities is a brief description and shall be read in conjunction with specifications and drawings.

Removal of POP covering and carting away all unwanted material including POP.

The rates quoted by the Tenderer will be deemed to be for the finished work complete in all respects with accessories, fitting, mounting arrangements normally provided with such equipment and/or needed for execution, completion, safe operation of equipment as required through they may not have been specifically mentioned in technical specifications, drawings and/or schedule of equipment.

All minor Masonry, Carpentry and Civil works such as cutting opening in Masonry Walls, Internal Partitions, chasing on walls, etc. and making good the same to match existing works shall be provided by the contractor, whenever asked for by the **Architect**.

SCHEDULE OF QUANTITIES

All items of work contracted for shall be executed strictly in accordance with the description of the item in the Schedule of Quantities, relevant drawings and specifications read in conjunction with the appropriate Indian Standard specifications and conditions of the contract and established Engineering practices.

The rate for each item of work included in the schedule of quantities shall unless expressly stated otherwise include cost of:

All materials, fixing materials, accessories sequence of operations, appliances, tools, plant equipment, transport labor and incidentals required and completion of the work called for in the item and as per specifications and drawings completely

Wastage on materials and labor

Loading transporting, unloading, handling as necessary, hoisting to all levels, and setting, fitting and fixing the position, protecting, disposal of debris as directed and all other labor necessary and to fully complete the job in accordance with contract documents, good practice and recognized principles of trade laid down in codes of practice.

Liabilities, obligations and risks arising out of conditions of contract.

All requirements of specifications, whether such requirements are mentioned in the item or not shall be provided for the specifications and drawings where available are to be read as complimentary to any part of the schedule of quantities and any work called for in one shall be taken as required for all similar items.

In the event of conflict between Schedule of Quantities and other documents including the specifications the most stringent among them shall apply and the interpretations of the **Architects** / owner shall be final and binding.

The Contractor shall be paid for the actual quantity of work executed by him in accordance with the drawings at the accepted rates.

This schedule shall be fully priced and the extensions and totals duly checked. The rates for all items shall be filled in INK. The entries under amount column shall be rounded off to the nearest Rupee.

No alterations whatsoever is to be made either to the description of items in the Schedule of quantities or specifications unless such alterations, is clarified in writing by the **Architect** / owner. Any such alterations, notes or additions shall unless clarified in writing be disregarded when tender documents are considered. Any observation on BOQ should be made in the letter accompanying technical bid for proper consideration and on disfiguring or overwriting in the documents is permitted.

In event of an error occurring in the amount column of the schedule, as a result of wrong extension of unit rate and quantity, the unit rate quoted by the Tenderer shall be regarded as firm and the extensions shall be amended on the basis of rates.

All errors in totaling in the amount column and in carrying forward totals shall be corrected.

Unless otherwise stated, all measurements shall be taken in accordance with Indian standard for building of Measurements IS 1200 latest revision effective on the date of measurement for interior items as applicable.

Any errors in quantity of items from the contract schedule shall not vitiate this contract but shall be corrected and deemed to be a variation by the **Architect** / Owner.

DRAWINGS AND DATA

Within two weeks of placement of order/letter of intent contractor shall furnish the following data in triplicate for approval by **Architect** / Owner.

General arrangement drawing of the equipment on orders showing plan, elevations, and sectional views, mounting details.

Bill of materials.

Descriptive catalogues, characteristic curves, duty point efficiency factor and technical particulars of all the various equipment's offered.

SPARE PARTS AND MAINTENANCE FOR MATERIALS SUPPLIED

Tenderer shall offer along with the bid, duly recommended by manufacturer set of spare parts required for a period of 1 year's continuous operation. Itemized unit prices with exact quantities recommended for these spares shall be separately indicated for consideration of the Owner / **Architect**.

DOCUMENTS MUTUALLY COMPLIMENTARY

The several documents forming the contract are to be read as mutually complementary to each other and in case of ambiguities/ discrepancies, the same shall be explained and clarified by the **Architect** / Owner to the Contractor in what manner the work is expected to be carried out to meet the end requirements.

INSTRUCTIONS DURING EXECUTION

On the advice of the Owner, the **Architect** may issue further drawings and written instructions, details, directions and explanations collectively referred to as "Site instruction" in regard to:

Variations for modification of the design, quality or quantity of works as addition or omission or substitution of any works therein.

Any discrepancies in the drawings or between the schedule of quantities and/or specifications and/or drawings.

Removal from the site any material brought by the contractor and substitution of any other materials therefore.

The dismissal or removal from work of any person employed thereupon.

Removal/re-examination of any works executed in case of doubt of any nature.

Opening up for inspection of any work covered up without proper tests by the **Architect**.

Oversight on the part of the **Architect** / his assistant to disapprove any defective work or material shall not prejudice the Owner / **Architect**, thereafter to disapprove such work or materials and to order pulling down, replacement, removal breaking up or reconstruction.

The Contractor shall make his own arrangement for the engagement of all labor and shall be responsible for regulating their service conditions, work conditions in conformity with all Acts, Regulations, Rules or order of competent authority under relevant laws in force during the pendency of the contract.

Contractor shall indemnify the Owner from all claims relating to the workers/ staff/ sub-contractors, Salaries, Wages, Overtime, Leave, Provident Fund, Medical facilities, gratuity, Bonus or any other claim as applicable and stipulated in any statutory provisions, rules or order of competent authority.

All materials so far as procurable shall be of the reputed make in the category of manufacture and bear the stamp of quality of the Bureau Standards wherever applicable. The contractor shall furnish documentary proof, test certificates and guarantees as relevant to such materials from manufacturers, which shall match with the date of procurement.

SPECIFICATIONS GENERAL

These specifications are for work to be done, items to be supplied and materials to be used in the works as shown and defined on the drawings and described herein all under supervision and to the entire satisfaction of the **Architect** / owner.

The workmanship is to be the best available and of a very high standard, use must be made of specialist tradesmen in all types of work and necessary allowance must be made for the same in the rates quoted.

The materials and items to be provided by the contractor shall be the best of their respective kinds as specified in the tender and in accordance with the samples approved, where materials or products are specified in these specifications and/or Bill of Quantities by the name of the manufacturer of the brand name, trade name or catalogue reference, the contractor will require to obtain prior approval of the **Architect** / owner for using substitute material or product. The contractor shall produce all invoices, vouchers or receipted accounts for any materials if called upon to do so by the **Architect** / owner.

Samples of all materials are to be submitted to the **Architect** / owner for his approval before the contractor orders or delivers in bulk in the site. Samples together with their packing are to be provided by the Contractor free of charge and approved samples will be retained by the owner and designer for comparison with the materials which will be delivered to the site.

Should any materials be rejected by the **Architect** / owner, they will be removed from the site at the Contractor's expense. Also, the contractor will be required to submit specimen finishes of colors, fabrics, etc. for approval of **Architect** / owner before proceeding with the works. Should it be necessary to prepare shop drawings, and then four copies of such drawings shall be submitted for approval of the **Architect** who will retain two copies, all at the Contractor's expenses.

ELECTRICAL INSTALLATION:

The whole of the electrical installation shall be carried out by a major registered licensed Electrical Contractor's firm.

The electrical installation shall include for the supply of the whole of the materials and the work of fixing, necessary for the complete installation. The work shall be carried out in strict accordance with the latest edition of the Regulations for the Electrical Equipment of Buildings issued by the Institute of Electrical Engineers I.E. rules and to the satisfaction of and in accordance with rules, regulations, and requirements of the supply company and the Fire department all to the entire satisfaction of the **Architect** / owner.

The positions of all points and equipment shown on the drawings shall be assumed to be correct for the purposes of tendering, but it is the main contractor's responsibility to check the exact positions on the site before commencing the works.

NOTE: This specification is of the general type only and must be used in conjunction with the drawing of the particular item being made. Anything shown on the drawing and not in the specification must be compiled with, and vice versa.

SPECIAL CONDITIONS OF THE CONTRACT

1. Contractor shall Be going through all documents before quoting rates, and provide for necessary coats as may be included in either bill or material or specifications.
2. Contractor shall give prices in blank column. Entries in English made in ink. Arrive also the grand total must also fill in all * Rate only columns * and sign all corrections.
3. Contract shall be invalid unless all rates are filled and no extra conditions shall be submitted. Contractor shall sign by all the legal partners of the firm.
4. Each of the tender documents shall sign by the Contractor.
5. The Contractor whose tender is accepted shall be bound to implement the contract within eight days of intimation from Architect.
6. Work shall be dome night and day without extra charge, if necessary.
7. Contractor shall provide for stacking materials in such a way as to facilitate rapid checking of quantities.
8. Materials supplied by owner shall be used only in owner's site.
9. Contractors shall pay any local charges relating to execution of work.
10. Contractor shall arrange for all wastage.
11. Contractors shall arrange for all temporary connections.
12. No extra shall be paid, quantity sheets and drawings both to be considered jointly and Architect is the final authority for the interpretation.
13. Site instruction shall be deemed for proper execution and shall be carried out without extra charge.
14. Order book with numbered pages shall be kept on site. Contractor shall carry out all instruction's properly.
15. Contractor shall insure whole work against fore, PIC and third-party insurance.
16. The contractor shall submit and get approval of the samples of all the materials and work item from the Architect or his authorized representative well in advance before commencing the bulk of work. The rest of the work shall be completed only on the express approval of the Architect.
17. Work shall be carried out as per specifications in tender schedules / C.P.W.D specification 1977 Volume I & II & along with the latest correction slips and the relevant Indian Standard Codes of practice & of as specified by the Architect. In case of doubts the decision of the Bank. Shall be final and binding on the contractor.
18. The General conditions of contract and standard contract form of the work will be followed as per Circular No. ADV/ © /Gen-53/71/CIR/ 103-73 dated 6th February 1973 issued by the Bureau of Public Enterprises, Ministry of Finance with latest modifications and as amended by bank. In their Paint Work procedure to suit their requirement.
19. Contractor must make arrangement for storage of cement at his cost.
20. structure injury to personnel during the progress of the work and he shall be liable to pay such compensation or may be decided by the Engineer-in charge in respect of such damages/ injuries. The contractor should rectify the damages at his cost of entire satisfaction of the Architect / bank engineer.
21. The serviceable materials out of the dismantled materials will be property of Bank and shall be properly streaked by the Contractors as directed by the Engineer-in-charge on the serviceability on the contractor.
22. All labor employed by the Contractor shall be covered by works men's compensation Act. Any death, injury of mishap to the workman of the Contractor will entirely be at the Contractor's responsibility and Bank shall not be liable to pay any damages for the same.
23. The Contractor shall give his permanent account number (from the income tax department).
24. Guarantee of minimum 10 years will have to be given by the Tenders for the water proofing treatment and indemnity bound for the purpose to be executed before release of the final payment / Security Deposit.
25. The work shall be carried out as per Indian Electricity Rules.
26. Appointed Architect by Union Bank of India will be Project Architect for the subject work.
27. The contractor may be required to make his own arrangement for water and electricity for the work.
28. The drawing contains the sketches showing salient details at various scales indicating the ascent of work & specifications must be followed, these can be modified from time to time in accordance with technical requirement at the site.
29. The prospective contractor, on intimation on acceptance of tender must submit progress net- work of the complete work based on bar-chart within four days as such of modified with the consent of the contractor shall form a part of the agreement.
30. The work shall be of highest standard, both as regard its design & workmanship. Modern tools & first-class latest techniques

shall be employed for its execution.

31. The contractor should employ adequate labor to complete the work within the specified time. No claim for the labor shall be entertained. The contractor shall also make his own proper arrangement for welfare, housing & safety of his material & labor.
32. The Architect shall have full powers to get the material or workmanship etc. inspected & tested by an independent agency for its soundness & adequacy at the cost of contractor.
33. The contractor shall examine all drawings before commencing the actual work & report to the Architect any discrepancies for omission & shortcomings in the drawings or when they conflict with works, or with each other.
34. The contractor shall visit the site of the work & shall satisfy himself as to the conditions under which the work has to be performed. He shall also check & ascertain the location of the existing structure or equivalent or another, which may affect the work. No claim, made in ignorance or misunderstanding or the site conditions or a ground or insufficient description shall be entertained.

Union Bank of India

FURNITURE WORK: GENERAL SPECIFICATIONS

This specification is for the work to be executed items to be supplied and materials to be used in the works as shown and defined on the drawings and described here in all under the supervision and to the satisfaction of the Architect/ Bank. the workmanship is to be the best available to a high standard. Use must of specialist tradesmen in all aspects of the works, and allowance must be in the rates for doing so.

the materials and items to be provided by the contractor shall be the best of their respective kinds, approved by the Architect in accordance with any samples which may be submitted for approval and generally in accordance with the specification. Where materials or products are specified in this specification and/ or bill of quantities by the name of the manufacture or the brand trade name or catalogue references the contractor will require to obtain the approval of the Architect/ Bank before using a material or product other than the specified. The contractor shall produce all invoices, vouchers or receipted accounts for any materials of called upon to do so by the Architect.

Sample of all material are to be submitted to the Architect for his approval before the contractor orders or delivers in bulk to the site. Also, the contractor will be required to submit finishes to colors, fabrics etc. for the approval of the Architect before proceeding with the works. Should it be necessary to prepare shop drawings, then four copies of such drawings shall be submitted for the approval Architect who will retain to copies, all at the contractor's expenses.

1. MATERIALS

The materials shall be of the best approval quality obtainable and shall comply with the respective Indian Standard Specification.

If directed, materials shall be tested in any approved Testing Laboratory and the test certificates in original shall be submitted to the Architect and the entire charges for repeated testes, if ordered shall be borne by the Constructor.

It shall be obligatory for the contractor to furnish certificate, it demanded by the Architect from manufacturer of the material supplier that the work been carried out by using their material and as per their recommendations.

All materials supplied by the Bank/ any other specialist firm shall be properly stores and the Contractor shall be responsible for its safe custody until they are required on the works and till the completion of work.

Unless otherwise shown on the Drawings or mentioned in the "Schedule of Quantities" or Special specifications, the quality of materials, workmanship, dimensions etc., shall be as specified herein under.

The contractor without any extra cost for carrying out field-test on materials shall provide all equipment's and facilities.

2. GLASS:

All glass shall be float glass of the best quality, free from specks, bubbles, smokes, veins, air holes, blisters and other defects.

The kind of glass to be used shall be as mentioned in the item or specification or in the special provisions or as shown in detailed drawings thickness of glass panel shall be uniform. All glass to be approved manufacture complying with IS: 3548-1966 or as per approved quality and sample.

The compound for glazing to metal is to be special non-hardening compound manufacture for the purpose and of 9 brands and quality approved the Interior Designer.

In cutting glass, proper allowance shall be made for expansion. Each square of glazing to be in one whole sheet and after cutting the edges to be properly filled.

On completion, clean all glass inside and out, replace all cracked scratched or broken panes and leave in good condition to the satisfaction of the Architect.

The contractor shall furnish all labor, materials, and equipment's required for the installation of glass and glazing items. The glass shall be of the type, quality and substance specified in the bills of quantities.

In case of the glass being supplied by the owners, the contractor shall take the delivery of the glass at site and shall be responsible for proper handling and stacking. We shall insure glass against theft, fire, etc.

The contractor shall replace at his own expense all broken, damaged or disfigured glass caused in the execution of the work of faulty installation, before the virtual completion of the work. Patterned of translucent glass shall be 12 mm. In thickness and shall be approved by the Architects. The putty used for glazing metal door, window or ventilator shall conform to I.S. 420:1953.

Before installation of the glass, the contractor shall ensure against the following

1. All glazing rebates shall be square, putty, true in plane, clear, dry and free of dust.
2. The frames shall be adjusted before glazing. The weight of the glass in side hung casement causes it to drop slightly on its hinges. Before glazing the shall be set in slightly high position in its frame.
3. Glass edges shall be clean and cut to the exact size, chipped or damaged edges shall be rejected.

4. Sashes shall be glazing in the closed position and shall not be open till the putty is set.

The glass shall be set in teak wood beading or metal glazing chips and so installed to achieve water lightness.

The platter glass shall be bedded on trips of leather or felt turned over the two sides of the glass to form packing between the glass and the metal coating. The ground glass shall be getting with smooth surface outside.

Glazing large panes of glass, or when heavy wind pressure is experienced, glazing bead may be used instead of front putty. In this case putty shall be applied to the face of the bead, which is in contact with glass. Putty would also be necessary, at the back.

Beads shall be of timber, rustproof steel or aluminum and shall have mitered corners. The position and size of the bead may depend on the thickness of glass used. The beads shall be fixed with screws 0" apart.

On completion of the job, all glass shall be thoroughly cleaned. All paint or other marks to be removed.

3. FASTENINGS AND HARDWARE:

3.1. The fixtures and fastenings, that is, but hinges, tined strap hinges, shading door bolts, door bolts, tower bolts, door latch, bath room latch, handles, door stoppers, casement window fasteners, casement stays and ventilators catch shall be made of the metal as specified in the item or its specification.

3.2. They shall be of iron, brass, aluminum, chromium plated iron, chromium plated brass, copper oxidized iron copper oxidized brass or anodized aluminum as specified.

3.3. The fixtures shall be heavy type. The fixtures and fastenings shall be smooth finished and shall be such as will ensure ease of operation.

3.4. The samples of fixtures and fastenings shall be got approved as regards quality and shape before providing them in position.

3.5. Brass fittings should be proper polish finished.

3.6. Screws, nails, bolts, will be of brass or non-corrosive metal. In hardware, they will match with the hardware items.

3.7. Nails, in a finished surface shall be nearly punched and the holes filled with wood filler matching the finish. Screws, in a finished surface will be round head. Round head or sunk beneath the surfaces and the hole plugged with a wood plug with matching color and grain of the wood surface, unless especially detailed.

4. HARDWARE

Hinges, locks, latches, door tracks etc. shall be as specified and as well as possible, by the manufacturer specified. In any variation of this quality of the substitute shall be equal to or better than the original specified, and the samples shall be submitted to the Architect for prior approval.

HARDWARE AND METALS

The hardware throughout shall be of approved brand and supply well-made equal in every respect to the samples deposited with the Architect. The contractor may be required to produce and provide samples many different sources before the Architect is able to make the decision and he should allow in his rates for doing so.

Fittings generally are to match the finish of the article to be fixed and to be rounded or flat headed or counter sunk as required.

Screws are to match the finish of the article to be fixed and to be rounded or flat headed or counter sunk as required.

Cover up and protect at the brass or powder coated surfaces with a thick grease or other suitable material, renew as necessary and subsequently clean off and clear away on completion.

All steel, brass, bronze, aluminum and stainless-steel articles shall be submitted to a reasonable test for strength, if so, required by the Architect at the contractor expenses.

DOOR CLOSERS

The overhead door closer shall be of EFFICIENT GADGET make of E.G. As approved by the Architect. The overhead door closer shall be of color as approved by the Architect. Fixing of the overhead door closer shall be done by and experienced worker preferable from The Branch Manager supplier of the item.

After successful installation of the overhead door closer the same shall be checked for speed door closing. The contractor shall make necessary adjusted operating mechanism as per manufacturer's guidelines to arrive at most suitable operating speed. The selected operating speed should remain constant on all repeated operations. If an overhead door closer is found to lose its adjusted operating speed often during warranty period then the shall have to be replaced with a new piece without charging any extra.

In case of a steel frame door the overhead door closer shall to be mounted on a special plate supplied by the manufacturer. No extra payment shall be due for such mounting plate.

The rate shall include all materials, labor, required civil work etc. complete and shall be paid per no. of overhead door closer/s installed.

5. TIMBER:

Timber generally is to be the best of its kind, well and properly seasoned, of mature growth, free from worm holes large loose or dead knots or other defects and sawn die square and will not supper warping, splitting or other defects through improper handling.

The hardwood is to be C.P. teak weighting not less than 45 lbs. per cubic foot with moisture content not exceeding 12% to 14%. The moisture content of timber shall be determined according to method described in paragraph 4 of IS:287 for "Maximum permissible moisture content of Timber used for different purpose in different zones".

In measuring cross-sectional dimensions of the frame pieces tolerance up to 1.5 mm shall be allowed for each planned surface.

Superior Quality Indian Teak Wood:

Superior quality Indian teak wood means Dandeli, Balarshah and Malabar Burma teak. It shall be of good quality and well-seasoned. It shall have uniform colour, reasonably straight grains and shall be free from large, loose dead knots, cracks, shakes, warp, twists, bends, borer, holes sal wood or defects of any kind. No individual hard and sound know shall be more than 1 cm. In diameter and aggregate area of all knots shall not exceed 1/2% of the area of the piece. It shall be close gained and there shall not be less than 6 growth rings per 2.5 cm width.

First Class Indian Teak Wood:

First class Indian teak means C.P. and Bulsar teak of good quality and well-seasoned. It shall have uniform color reasonably straight grains and shall be free from large, loose, dead knots, cracks, shakes, warp, sound knot shall be more than 2.5 cm. In diameter and aggregated area of all knots shall not exceed 1% of the area of the piece. There shall not be less than 4 growth rings per 2.5 cm width.

Second Class Indian teak Wood:

Second class Indian teak wood shall be similar to first class Indian teak wood except knot up to 4 cm diameter and aggregate area of all knots up to 11/2% of area of the piece shall be allowed. There shall not be less than 4 growth rings per 2.5 cm width.

5.1 Timber is to be cut to the required sizes and lengths as soon as practicable after the works are begun and stored under cover so that the air will circulate freely around it. Joinery is to be prepared, immediately after the placing of the contract, framed up (but not bonded) and stored until required for fixing in position, when it is to be bonded and wedged up. Any portions that warp or develop shakes or other defects are to be replaced before wedging up. The whole of the work is to be framed and finished in a proper and workman like manner, in accordance with the detailed drawings, and fitted with all necessary motets straps, belts screws etc. Running bonded joints are to be cross-tongued with teak tongues and where over 1-1/2" thick double cross tongued. Joiner's work generally is to be finished with fine class papered surfaces unless otherwise specified.

Templates boxes and molds shall be accurately set out and rigidly constructed so as to remain accurate during the time they are in use.

Grounds are to be clean shown, free from large knots, splayed as required, plugged and fixed to walls etc. at 1'6" centers.

Wood plugs are to be put cut on twist. Patent wall plugs or plastic filling may be used in lieu of wood plugs with the approval of the Architect.

All unexposed surfaces of timber e.g. false ceilings, backings fillets back of doors frames backs of doors frames, cupboard framing, grounds etc. are to be treated with two coats of approved timber preservative like solignum, kirticite, termiseal or Castrol or vacuum pressure impregnated with and approved water-soluble timber preservative before fixing or bedding.

Carpentry and Joinery:

The carpenter and joiner shall include the finishing of all labor, materials, equipment, and appliances required to complete the work including the installation of hardware as per the drawing.

The timber shall be of the quality as described on the drawings or in the bills of quantities, shall be seasoned and uniform in texture, free from fungal growths, knots, wanes, open shake borer holes, rot decay, discoloration, soft or spongy spots, holes, rot, decay, discoloration, soft or spongy spots, hollow pockets, patch or box heart and all other defects.

Skilled workmen, using proper tools, shall carry out all the carpenter's work. All joints shall be securely nailed without splitting the wood. Wherever it is necessary the members shall be lapped of joining by G.I Stapes or extra wood blocks. All joints and nailing shall be done in neatness, and shall be approved by the Architects. All assembly be exactly at right angles.

Finish woodwork and joinery including doors shall be surfaced with straight without any warp of bow and shall have smooth. Well-planned faces at right angles to each other. The frame members shall be placed on the three sides exposed at right angles to each other.

All joinery work shall be securely mortised and tongued with synthetic resin conforming to I.S.851-1957. Heads, posts, transoms, millions of door and window frames shall be made out of single pieces of timber only. The heads and posts shall be thought – tenoned into the mortises not less than ½". Solid wood panels of not less than 5" and not more than 8" in width shall be used and jointed together with tongue groove joint.

All interior wood finish doors, cabinet work shall be smoothly treated and sanded after erection, until all the defects are entirely removed. Assembled door frame without sills shall be fitted with temporary stretchers. All exposed wood and plywood shall be straight-grained method grain and color and shall be approved by the Architects. Interior wood finished doors cabinets and other fixed wooden equipment's shall be properly installed, level plumb and true. But joints shall be avoided wherever possible, if unavoidable the joint shall be leveled. All exterior angles shall be mitered. Adjoining interior wood shall match and harmonies. All woodwork in contact with masonry shall be painted with bitumen paint or red oxide paint.

5.2 JOINTS:

All joints will be standard, mortised and tenon, dovetail, dowel, cross-halved, metered, tongued and grooved and rebated. Nailed or glued but joints, will not be permitted exceptional cases, ailed but joints will not be accepted. All joints shall be smeared with white lead.

Whenever solid wood is specified it shall be as per I.S.I and of good quality. The type of wood shall be got approved before collecting the same on site. Fabrication of wooden members shall be started only after approval. It shall be free from large, loose, dead of cluster knots, flows, shakes, warps, bends or any other defect. It shall be uniform in substance and of straight fibers as far as possible. It shall be free from rats, decay, harmful fungi and other dejects of nature which will affect the strength, durability of it usefulness for the purpose for which it is required. The color of wood shall be uniform as far as possible. The scantlings plank etc. shall be seen in straight lines and planes in the direction of grain and of uniform thickness.

5.3 FIRST CLASS TEAK WOOD:

First class teak wood shall no individual hard and sound knots, more the 6 sq. cm. In size and the aggregate area of such knots shall not more than 1% of area of piece. The timber shall be closed grained.

5.4 SECOND CLASS TEAK WOOD:

No individual hard and knots shall be more than 15 sq. cm in size and aggregate area of such knot's shall not exceed 2% of the area of piece.

6. PAINTING

General: Wherever scaffolding is necessary, it shall be double scaffolding.

The surface shall be thoroughly brushed free from mortar droppings, and foreign matter. All steel work shall be cleaned of loose rust, mill scales, etc. so as to expose the original surface. All broken edges, cracks, loose-plaster and wavy surface be brought up either by patch plasterwork or by plaster of Paris.

All materials viz. Dry distemper, oil bound distemper, oil paint, flat oil paint, synthetic enamel paint, plastic emulsion paint, cement primer, red lead and other primers and metallic paints shall conform to respective I.S. specifications and shall be obtained from approved manufacturers.

7. Painting- Flat / Plastic Emulsion etc.:

Ready mixed flat oil paint, plastic emulsion paint, ready mixed synthetic enamel paint, aluminum paint, etc. shall be brought in original containers and in sealed tins, if for any reason thinner is necessary, the brand and quality of thinner recommended by the manufacturer or as instructed by the Architect shall be used. The surface shall be prepared as specified above and a coat of approved primer shall be applied. After 24 hours drying, approved or specified quality paint shall be applied evenly and smoothly. Filler putty coating may be given to give a smooth finish. Each coat shall be allowed to dry out thoroughly and then lightly rubbed down with sand paper and cleaned of dust before the next coat is applied. Number of coats shall be as specified in the item and if the finish of the surface is not uniform, additional coats as required shall be applied to get good and uniform finish at no extra cost. After completion no hair marks from the brush or clogging of paint puddles in the corners of panels, angles or moldings etc. shall be cleaned of stains.

Pigmented priming coat (emulsion thinned with water) followed by three or more finishing coats of plastic emulsion paint. Pasted filler to be applied every coat exempting the final finishing coat and sanded.

When the final coat is applied, if directed the surface shall be rolled with a roller or if directed, it shall be stippled with a stippling brush.

8. ENAMEL PAINTS

Oil paints shall be of first quality and of the specified color and shade, and as approved. The ready mixed paints shall be only used. However, if ready mixed paint of specified shade or tint is not available while ready mixed paint with approved strainers will be allowed. In such a case, the contractor shall ensure that the shade of the paint so allowed shall be uniform.

All the paints shall meet with the following general requirements:

- i. Paint shall not show excessive setting in a freshly opened and shall not easily redispersed with a paddle with smooth homogeneous stage.
- ii. Paint as revived shall brush easily, possess good leveling properties and show no running or sagging tendencies.
- iii. The paint shall not skin within 48 hours in three quarters filled closed container.
- iv. The paint shall dry to a smooth uniform finish free from roughness, grit, unevenness and other imperfections.

Ready mixed paints shall be used exactly as received from the manufacturers and generally according to their instruction and without any admixtures what so ever.

9. POLISHING VARNISHING

a. French Polishing:

French spirit polish shall be approved make conforming to I.S.:348. If it has to be prepared on site, dissolving 0.7 Kg shall make the polish. Of best shellac in 4.5 liters of methyl spirit without heating. To obtain required shade pigment may be added and mixed.

Surface shall be cleaned. All unevenness shall be rubbed down smooth with sand paper and well dusted. Knots, if visible, shall be covered with a preparation of red lead and glue. Resinous or loose knots and gaps shall be filled with seasoned timber pieces and made level with rest of the surface. Holes on surface shall be filled with putty made of whiting and linseed oil. Surface shall be given a coat of filler made of 2.25Kg. Of whiting in 1.5 liter of methyl spirit. When it dries, surface shall again be rubbed down perfectly smooth with sand paper and wiped clean. Piece of clean fine cotton cloth and cotton wool into shape of pad shall be used to apply polish. The pad shall be moistened with polish and rubbed hard on the surface applying the polish sparingly but uniformly and completely over the entire surface. It shall be allowed to dry and another coat applied in the same way. To give furnishing coat the pad shall be covered with a fresh piece of clean fine cotton cloth, slightly damped with methyl Spirit and rubbed lightly and quickly with a circular motion, till the finished surface attains uniform texture and high glass.

b. Wax Polishing:

Wax polish shall either be prepared on site or obtained ready made from market. Polish made on the state shall be prepared from a mixture of purr bees wax, linseed oil, turpentine oil and varnish in the ration or 2:1 ½:1: ½ by weight. The bee wax and the boiled linseed oil shall be heated over a slow fire. When the wax is completely dissolved the mixture shall be cooled till it is just warm, and turpentine oil and varnish added to it in the required proportions and the entire mixture is well stirred.

Surface shall be prepared as described under "French Polishing" except that the final rubbing shall be done with sand paper, which has been slightly moistened with linseed oil.

Mixture or polish shall be applied evenly, with a clean cloth pad in such a way that no blank patches are left, and rubbed continuously for half an hour. When the surface is quite dry a second coat shall be applied in the same manner and rubbed continuously for an hour or until the surface is dry. Final coat shall then be applied and rubbed for two hours or more if necessary, until the surface has assumed a uniform and is quite dry showing no sign of stickiness when touched. Glass rubbing must be continuous and with uniform pressure and frequent change is direction.

c. Varnishing:

Surface shall be prepared as described above. After preparation of surface, two coats of clean boiled linseed oil shall be applied at sufficient interval of time. After the linseed oil has dried two coats of varnish obtained from approved manufacture shall be applied at sufficient interval of time. If the surface fails to produce the required glass an additional coat shall be applied without any extra cost.

10. MELAMINE FACED PARTICLE BOARD:

It should be three-layered wood-based particleboard, such as Nova pan melamine paced pre- laminated on both sides. Particleboard should be ISI 3087 FPTH (type II, 1965) marked on edges and should impart good confirm to German Din standard Viz DIN 66761. It should impart good bending strength and screw holding strength. Melamine faced surface should has resistant to crack at 100 c and should pass cigarette burn test.

11. PLYWOOD

Plywood for general purpose shall confirm I.S. 303-1975. It shall be formed with 0.8 mm. Th. Commercial face veneers and 1.5 mm. Th. Intermediate veneers in two opposite grain direction shall be 1:1. The moisture content shall not be more than 12.5% by mass. It shall either be or Green ply, V.I. ply make or other equivalent approved make. Where B.W.P. grade is specified it should be boiling waterproof confirming to I.S. standards.

12. LAMINATES:

All the laminate to be used shall be of 1.5 mm (or where specified) thickness in approved the color and shade as proved and specified by the Architect. It shall be matt finish manufactured by Greenlam, Home mica. Or its equivalent as per sample shown by the consultant unless otherwise specified. It shall satisfy all the I.S. standards for melamine coated laminated fiberboards before the use of such fiberboard laminated. The contractor shall have to take approval of the department of each sheet of the laminates.

Union Bank of India

TECHNICAL SPECIFICATIONS (MAKES/MODELS)

LIST OF APPROVED MAKES OF MATERIAL

The following are approved brand makes/manufacture's makes listed below. In case it is established that material as listed below is not available in the market, approved equivalent material and finished off any other specialized brand names/manufacture's makes may be used as per approval of BANK/Architect/Consultant. Contractors are instructed to submit the approved make list of items which they are using at site before starting the work.

SR. NO	ITEM	APPROVED MAKE
A	CEMENT	
1	GREY CEMENT	AMBUJA, ACC, GRASIM, ULTRATECH (L & T)
2	WHITE CEMENT	JK, BIRLA
B	BRICKS	GOOD QUALITY APPROVED BY EIC
C	TILES (GLAZED/CERAMIC/VITRIFIED)	
1	GLAZED TILES	NITCO, SOMANI, BELL OR APPROVED EQUIVALENT
2	CERAMIC TILES	NITCO, SOMANI, BELL OR APPROVED EQUIVALENT
3	VITRIFIED TILES	SOMANI, NITCO, EURO, ASIAN OR APPROVED EQUIVALENT
4	RUSTIC VITRIFIED TILES	VERMORA OR EQUIVALENT OR APPROVED EQUIVALENT
D	PAINTS	ICI, ASIAN, DULUX, BERGER, NEROLAC, JOHNSON & NICOLSAN
1	ANTI CORROSIVE PAINT	TIKITAR, FINCOAT
2	RED OXIDE	ASIAN, DULUX, NEROLAC
3	POLISH	ASIAN MELAMINE
4	EXTERIOR PAINTS	DULUX WEATHERSHIELD OR APP. EQUIVALENT
5	ENAMEL PAINT	ICI, DULUX, ASIAN, NEROLAC
E	FALSE CEILING	
1	GYPSUM BOARD	GYPROC (SAINT GOBAIN)
2	FRAMING WITH COMPLETE SYSTEM	GYP STEEL ULTRA (SAINT GOBAIN), RAMCO FUJI
3	HILUX BOARDS	RAMCO OR APPROVED EQUIVALENT
4	MINERAL FIBRE TILES CEILING WITH COMPLETE SYSTEM	ARMSTRONG/SAINT GOBAIN/USG
F	SANITARYWARE	
1	WASH BASIN, URINALS, W.C.	JAQUAR, CERA, PARRYWARE.
G	S.S. SINK	NIRALI OR EQUIVALENT
H	SANITARY FITTINGS	
1	BIB/STOP/ANGLE COCK & OTHER C.P. BRASS FITTINGS	JAGUAR (FLORENTINE SERIES OR AS SPECIFIED IN BOQ)
I	PIPE/PIPE FITTINGS	
1	C.I. PIPES	NECO

2	G.I. PIPES	SURYA, TATA OR EQUIVALENT
3	PVC PIPES & FITTINGS	ASTRAL OR APPROVED EQUIVALENT
4	GULLY TRAP	ASTRAL OR APPROVED EQUIVALENT
5	C.I. GULLY TRAP COVER	NECO OR APPROVED EQUIVALENT
6	INSPECTION COVER	NECO OR APPROVED EQUIVALENT
J	GLASS/MIRROR	SAINT GOBAIN, MODI FLOAT
K	WATER PROOFING	
1	WATER PROOFING COMPOUND/CHEMICAL	LATICRETE, PIDILITE, CHEMBOND
2	HARDENERS	IRONITE, FERROK, HARDONITE
3	TILE FIXING ADHESIVE	LATICRETE, FAIRMATE, PIDILITE OR EQUIVALENT
4	SEALANT	FOSROC, GE SILICONES
L	FURNITURE ITEMS	
1	LAMINATES (IS-2046) / VENEER	GREEN LAM / CENTURY / SILICON-EVOKE / BELL / VIR / EURO / SAMRAT / FORMICA / SUNDEK OR APPROVED EQUIVALENT
2	COMMERCIAL PLY (IS-303) / WATERPROOF PLY (IS-710) / BLOCK BOARD (IS-1659) / FLUSH DOOR (IS- 2202)	ANCHOR / AMUL / EURO / SILICON – EVOKE / GREEN OR APPROVED EQUIVALENT BY EIC.
3	ADHESIVES	FEVICOL / BLUECOAT
4	LOCKS	
	AUTO LATCH LOCK	P-ALL1-22 (EBCO)
	MULTIPURPOSE GROUP LOCK	E-MPL1-22 / E-MPL1C-22 (EBCO)
	NIGHT LATCH	8812 (GODREJ)
	CYLINDRICAL LOCK (SS MATT FINISH)	3792-WITH KEY AND 3786-KEYLESS (GODREJ) / C120SS (EUROPA)
	MORTISE DEAD LOCK (TWO WAY)	8815(GODREJ)
	MORTISE LOCK WITH DOOR HANDLE	MATIZ 8083(GODREJ)
5	DRAWER CHANNELS	
	TELESCOPIC CHANNELS (ZINK PLATED)	STDS35(I)35/ STDS25(I)35/ STDS50(I)35/ STDS60(I)35 (EBCO)
	BOTTOM CHANNELS (POWDER COATED)	BMDS 35/ BMDS 37/ BMDS 55/ BMDS 60 (EBCO)
6	GENERAL HARDWARE	SS MATT FINISH
	DOOR STOPPER	I) BLACK/IVORY/BROWN/SILVER COLOR POWDER COATED DS1 (EBCO) II) SPRING TYPE BLACK/BROWN/IVORY COLOR POWDER COATED (ECGL'S STERLING)
	'D' BRACKET	50X12 MM (OSWAL)
	HINGES	I) 3"/4"/5"/6" 1.8MM TH. SS MATT FINISH (SUZU) II) 75X12X19 1.2 MM TH. SS MATT FINISH FOR STORAGE (SUZU) III) AUTO CLOSE HINGES – SLIP ON HINGE- EURO / CLICK ON HINGE-I (EBCO) FOR STORAGE

	HANDLES 'D' OR 'C' TYPE	1) 3"/4"/6"10MM DIA SS 202 MATT FINISH (ANJALI)
	TOWER BOLT	3"/4"/6"/8" BRASS EXTRUDED SS MATT FINISH (OSWAL)
	SLIDING CHANNEL	EBCO MAKE APPROVED BY ARCHITEC/BANK.
7	FLOOR SPRING	
	60 KG	7477 (GODREJ) / M-74 (HARDWYN)
	80 KG	8293 (GODREJ) / M-74 (HARDWYN)
	100 KG	8294 (GODREJ) / M-76 (HARDWYN)
8	DOOR CLOSER	
	60 KG	DOUBLE SPEED 8292-SILVER, 7325- GOLDEN (GODREJ) / SCORPIO (HARDWYN)
	FIRE RATED 60 KG	1938 (GODREJ) / TRITON (HARDWYN)
9	PATCH FITTINGS FOR DOOR AND FIXED GLASS PARTITION (TOP/BOTTOM PATCH, PIVOT, PATCH LOCK, L ARM, L CONNECT, CONNECTOR, FLOOR SPRING, HANDLE, PLASTIC PROFILE)	GODREJ / XL C SERIES(DORMA) / OPF SERIES (OZONE) OR APPROVED EQUIVALENT
10	GLASS / MIRRORS	SAINT GOBAIN / MODI
11	ALUMINUM SECTION	JINDAL / INDAL / BANCO
12	WINDOW BLINDS	VISTA / AEROLUX/HUNTER DUGLUS / MAC
13	POLISH / PAINT	ASIAN PAINTS / BERGER / NEROLAC
14	PARTICLE BOARDS	NOVAPAN / DECO BOARD
15	COMPUTER ACCESSORIES	
	KEYBOARD TRAY WITH MOUSE TRAY	KTE-1-25M (EBCO)
	CPU HANGER/ SHELF	SIDE MOUNTED IS CPU HL SM (INNOFITT) /CPUSM(EBCO) , 4/2-SMCS (ZIPCO)
	CABLE MANAGER (60MM)	I) METAL - CO60ZN1(EBCO) II) PVC - CO 60 (EBCO) BLACK/IVORY/GREY COLOR
16	ACP PANEL	TIMEX / ALU DECOR / EURO OR APPROVED EQUIVALENT
17	FOAM	SLEEPWELL / FEATHER FOAM
18	WALL PAPER	WK STONE (GAEOLD PADRA ROAD I) / EXCEL (STREAMLINE) OR APPROVED EQUIVALENT
19	WHITE FILM FOR GLASS	CRYSTAL / SONA MAKE VINYL FROSTED FILM

Note:

- (I) In case of non-availability of any material of specified make, the alternative should be used only after its due approved by the Bank/Architect.
- (II) The last decision of the choice of any of the agency rest with Architect / Bank.
- (III) For all items only exposed elevation measurement shall be taken for bill amount hidden supporting members of furniture / partition will not be taken in to account.

LIST OF INDIAN STANDARDS REFEREED TO

1. I.S. NO. 1200 – Latest measurement of building and civil engineer work.
2. I.S. NO. 287 – 1973 recommendation for maximum permissible moisture content of timber used for different purpose in different climatic zones
3. I.S.NO. 1141 – 1973 code of practice for seasoning of timbers.
4. I.S.NO. 6534 – 1971 guiding principles for grading and inspection of timber.
5. I.S.NO. 1200 (part XXI) 1973.
6. I.S.NO. 3845 – 1966 code of practice for joints used in wooden furniture.
7. I.S.NO. 4450 – 1967 wooden flush doors. Type to method of test for.
8. I.S.NO. 4970 – 1973 key for identification of commercial timber.
9. I.S.NO. 3364 (part II) – 1975 methods of measurements and evaluations of defects in timber, part II converted timber.
10. I.S.NO. 1708 – 1969 methods of testing shall clear specimens of timber.
11. I.S.NO 6342 – 1971 Rose wood logs for production of sliced veneers.
12. I.S.NO 5248 – 1969Teakloges for production of sliced veneers.
13. I.S.NO. 2202 (part I) 1973. Specification for wooden flush door shutters (solid core type cat I plywood).
14. I.S.NO. 2338 (part 1) 1967 code pf practice for finishing of wood-based materials part 1 operations and workmanship.
15. I.S. No. 7360 – 1975 Methods of sampling of plywood.
16. I.S.NO. 303 – 1975 Specification for plywood for general purposes.]
17. I.S.NO. 3129 – 1965 Specification for article board for insulation purposes.
18. I.S.NO. 3513 – 1966 (part – III & part iv) High and medium density wood-based laminates part III general purposes. Part IV sampling test.
19. I.S. NO. 1659 – 1979 Block boards.
20. I.S.NO. 7916 – 1974 Decorative plywood using plurality or veneers for decorative faces.
21. I.S NO. 3478 – 1966 Height density wood particle boards.
22. I.S. NO. 1734 (part 1 to XX) Plywood method of test for
 Part I -General
 Part II -Plywood
 Part III -Battens
23. I.S.NO. 1328 – 1970 veneer decorative plywood.
24. I.S. NO 710 Marine ply.
25. I.S.NO 3087 – 1965 Wood particle boards (medium density)
26. I.S. NO. 3087 – 1965 Specification for synthetic rising adhesives for plywood (phonolic & Amino plastic)
27. I.S.NO. 2046 – 1969 Specification for decorative laminate.
28. I.S. NO. 8273 – 1976 Fibrous gypsum plaster boards.
29. I.S. No. 2095 – 1964 Gypsum plaster boards.
30. I.S.NO. 2542 (part 1) – 1978 Gypsum plaster concrete products, methods of test for part 1 – plaster and concrete.
31. I.S NO. 8272 – 1976 Gypsum plaster for use in the manufacture of fibers plaster boards.
32. I.S.NO. 2441 – 1963 Fixing coiling covering code of practice for.
33. I.S.NO. 2835 – 1977 Specification for flat transparent sheet glass.
34. I.S NO. 2395 (part 1) – 1966, 2395 (part 11) – 1967 painting to concrete masonry, plaster surface code of practice for part –1 operation and workmanship part II schedule.
35. I.S.NO. 3548 – 1966 Glazing in building code of practice.
36. I.S.NO 6279 – 1965 Specification for ready mixed paint brushing, matt or egg-shell flat finishing, interior.
37. I.S.NO. 137 – 1965 Specification for ready mixed paint brushing, matt or egg-shell flat finishing, interior to Indian standard colors as required.
38. I.S.NO. 133- 1975 Specification for ready mixed paint brushing, wooden coating, interior it Indian standard colors.
39. I.S. NO 129 – 1950 Specification for enamel interior (a) under coating (b) finishing.
40. I.S.NO. 120- 1950 Specification for ready mixed paint brushing, finishing interior oil glass, for general purposes to Indian standard colors.
41. I.S.NO. 533-1973 Specification for gum spirit of turpentine (oil of turpentine.)
42. I.S.NO. 101 – 1964 Methods of test for ready mixed paints and enamel.

43. I.S.NO. 75-1973 Specification for linseed oil, and refined.
44. I.S.NO. 77 – 1973 Specification for linseed oil, and refined.
45. I.S.NO. 124 (part1) – 1976 Specification for ready mixed paint brushing finishing semi- gloss for general purpose.
46. I.S.NO. 5884 – Specification for woolen carpets.
47. I.S.NO. 104- 1979 Specification for ready mixed paint Brushing finishing, zinc chrome primer.
48. I.S. NO 5391 – 1969 Adjustable metal chairs for use of typist and operators in telephone exchanges.
49. I.S.NO. 8756 – 1978 Ball catches for use in wooden almirahs.
50. I.S.NO 3499 – 1976 (part 11) chairs for office purposes metal revolving and tilting.
51. I.S.NO. 5416-1969 General purposes wooden chairs methods of test for.
52. I.S. NO. 6185 – 1971 High chairs specification and safety requirements for.
53. I.S.NO> 4116 – 1976 Joints used in wooden furniture code of practice for.
54. I.S.NO 3485 – 1966 Joints used in wooden furniture code of practice for.
55. I.S.NO. 7070- 1973 Shelving racks wooden (adjustable and non-adjustable) type.
56. I.S.NO 4414-1977 table tops (wooden)
57. I.S.NO. 5967-1969 Tables, wooden method of test for.
58. I.S.NO. 3564 –1975 Door closures (hydraulically regulated).
59. I.S.NO. 3564 – 1979 Drawer locks, cupboards and box locks.
60. I.S.NO. 7981 – (part1) – 1975 Glossary of terms relating to builder's hardware – part 1 locks.
61. I.S.NO. 204- (part 1 & 11) 1978 Tower bolts ferrous metals and non-ferrous metals.

Note: The various items to be used in the interior decoration work shall be of ISI standards. Whenever the items/ products do not have ISI marks standard, shall be got tested from Laboratory for its quality etc. necessary testing charges shall be borne by the contractor.

1. INSTRUCTIONS FOR CONTRACTORS -PLEASE READ THIS CAREFULLY

- a. The rate for items in schedule of Quantities must be given in words and figures. Amount of each items must also be entered in column and grand total of amount must be stuck out by the tenderer.
- b. If the tenderer is taken in favor of the company, a power of attorney in favor of the person who may have signed the tender for the company must accompany the tender.
- c. All pages of schedule of quantities etc. Should be initialed by the contractor.
- d. Discrepancies and adjustment of errors.

2. Any error in quantity or amount in schedule of quantities showing item or work to be carried out shall be adjusted in accordance with the following rules:

- a. In the event of a discrepancy between description in words and figures quoted by a tenderer in the rates column, the description in words shall prevail. In the event of an error occurring in the amount column of the schedule of quantities showing items of work, as a result of wrong multiplication of the unit rate and quantity, the unit rate shall be regarded, as firm and multiplication shall be amended on the basis of the rate.
- b. All errors in totaling in amount column in carrying forward total shall be corrected. c. Any rounding of amount against 'items' or in 'totals' shall be ignored. The tendered sum so altered shall for the purpose of the tender be substituted for the sum originally tendered and considered for acceptance.
- c. The clients/consultants have right to:
 - 1) Reject any no. of quantities in the tender.
 - 2) To decrease or to increase or to delete any quantity in the tender.
 - 3) In case extra items are there it will be settled as exact cost of material +exact cost of labour + 15% profit including wastage. NOTE: Unless these four sets are not submitted with the final bill then the final bill will not be certified.
 - 4) Contractor will have to use jarry cutter. The scope is making good the same.
 - 5) The contractor will have to use the first brand specified in the specified make list. If the same is not available then be has to take written prior approval of the consultant before using the same.

MANDATORY INFORMATION REQUIRED FOR PREQUALIFICATION OF THE BIDDER FOR INTERIOR FURNISHING WORKS FOR PROPOSED OLD PADRA ROAD BRANCH, UBI-VADODARA REGION.

- IMPORTANT:**
1. Please type or handwrite in capital letters.
 2. Attach copies of the supporting documents.
 3. Please use additional sheets if required.

SR.NO.	PARTICULAR	TO BE FILLED BY VENDOR
1	EMPANELMENT LETTER PROVIDED BY UNION BANK OF INDIA – VADODARA REGION FOR THE CURRENT YEAR. (Attach)	
2	CURRENT YEAR SOLVENCY CERTIFICATE. (NOT MORE THAN 12 MONTHS OLD) (Minimum Amount: Rs. 4.00 Lacs) (Attach)	
3	GST CERTIFICATE REGISTERED UNDER REGULAR WORK CONTRACT. PARTICIPATION OF COMPOSITE SCHEME VENDORS WILL NOT BE ACCEPTED FOR THIS TENDER. (Attach)	

Please Note: Bank has a right to prequalify/disqualify any application without giving any reason to any applicants.

I/We confirm that to the best of our knowledge this information is authentic and accept that any deliberate concealment will amount to disqualification at any stage.

SEAL AND SIGNATURE OF THE BIDDER/S.

DATE:
ADDRESS:

NO. OF ENCLOSURES:

PART B - PRICE BID

TENDER DOCUMENTS FOR INTERIOR FURNISHING WORK
FOR UBI - OLD PADRA ROAD BRANCH (EXISTING PREMISES),
UBI - VADODARA REGION.

Union Bank of India

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS

UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.

Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
1	WORKING TABLES				
1A	REUSE OF OLD TABLES				
	Removing, Shifting and fixing in position Working tables set Complete with Resizing, Alterations/fixing as per instructions and drawings. Cleaning of old tables (all surface) to be done.				
	Removing existing old Laminates from all exposed surfaces and providing new Bank's approved shade 1.0 mm tk. laminate (Using 6mm tk. Plywood wherever required). Removing & Refixing of Drawer Units as per instructions. Internal Surface to be oil painted-2 coats of approved shade. External Woods to be repaired/repolished with approved shade.				
	Rate shall be inclusive of all necessary approved fittings and any miscellaneous hardware items. Rate to include all labours/ transporation.				
	Dimensions of Tables/Counters may vary as per existing old furnitures.				
1A	MANAGER TABLE : Size - 6'-9" x 3'-3" x 2'-6"	1.00	SET		
1B	OFFICER/STAFF TABLE : Size - 5'0" x 2'-6" x 2'-6"	4.00	SET		
1C	STAFF TABLE : Size - 4'-6" x 2'-6" x 2'-6"	3.00	SET		
1D	SUB-STAFF TABLE: Size - 3'-6" x 2'-0" x 2'-6"	1.00	SET		
1E	CASH COUNTER - NEW	1.00	SET		
	<u>TABLE SIZE : TABLE TOP: (5'0"X2'9"X2'6") & TRANSACTION TOP: 5'0" x 1'4" at height of 3'10"</u> . Specifications of tables as mentioned above. Whereas, Drawer unit shall consist of 3 nos. of drawers. Height of Drawers will 6",6" & Balance below. 6mm com. ply. Finished with 1.0mm laminate as Divider in top 2 drawers for stacking of Currency.				
	L-Shape 18mm comm. Plywood fixed above table of size : 5'0" x 1'4" x 1'4" finished with 1.0mm laminate. Internal surface shall be finished with red tapestry on soft board of size 5'3" x 0'9" to be fixed on 18mm ply & 1.0mm Laminate.				
	<u>10 mm tk. approve make clear Toughened</u> float glass of size 5'0" x 1'0" & 5'0" x 2'0" (2" slit in between) with machined polished edges shall be supported on sides by D clips (Min. 4 nos. for single glass) complete as per design & bank's standards. Round/Oval shape Cutouts in glass shall be made for teller operations. No extra payment shall be made for Glass cutting/Openings.				
	Rate shall be inclusive of all necessary approved fittings like locks(Godrej make) and any miscellaneous hardware items. Partitions will be measure extra as individual items.				
2	WOODEN PARTITIONS - (FULL/LOW HEIGHT)				

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS**UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.**

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.

Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
	Note: Rate to include additional Sections & 18mm comm. ply./boxing to fix the Indoor AC units wherever required. Cutting/Opening in plywood for fixing of electrical fixtures, switchboards, A.C. piping to be done and neatly finishes the same. Laminate Grooves shall be made as per design/instruction with proper cleaning of adhesive and melamine paint finish. Providing pinup board of softboard covered with fabric and fixed in partition complete as directed.				
2A	FULL/LOW HEIGHT DOUBLE SKIN WOODEN PARTITION	450.00	SQ.FT.		
	Providing and fixing double skin full ht. partition shall consist of Aluminum Section 50 mm x 40 mm (Wall Thickness 2 mm) @ 2'0" C/C Both ways Horizontally and Vertically. The framing shall be finished with 12 mm thk. Commercial ply on both side 1.00 mm thk. approved shade Laminate shall be fixed from both sides of ply OR 8mm glass with white film as per design . Provide skirting in 1.00 mm thk. approved laminate to fixed as per drawing and direction. Steam beach wood to be used in all glazing perimeter duly natural polished. 19mm comm. ply to be used in back of A.C. indoor units complete with line, level & finish. Rate shall be inclusive of necessary hardware items, etc. Complete as per Instruction of Bank/Architect. <i>(The measurement of full ht. partitions shall be made up to false ceiling bottom lvl. only)</i>				
2B	BISON PARTITION	20.00	SQ.FT.		
	Specifications Same as above but using 8/10 mm tk. Bison Sheet and finished with paint.				
2C	OLD WOODEN PARTITIONS	222.00	SQ.FT.		
	All Wooden Molding/Glazing Perimeter to be polished. All glass to be provided with new glass film as suggested. Cleaning of all exposed surfaces needs to be done.				
	P & F of new 6mm ply on all exposed surface with approved laminate finish Wherever required. Finishing size of Partition fixed will be considered for bill measurement.				
	Removing, Refixing & Resizing of Old Partitions of existing size complete with cutting, additions & glass resizing.				
2D	RESHITING OF OLD PARTITIONS	280.00	SQ.FT.		
	All Wooden Molding/Glazing Perimeter to be polished. All glass to be provided with new glass film as suggested. Cleaning of all exposed surfaces needs to be done.				
	P & F of new 6mm ply on all exposed surface with approved laminate finish Wherever required. Finishing size of Partition fixed will be considered for bill measurement.				
3	WOODEN STORAGE UNIT				

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS**UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.**

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.

Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
	Providing and laying storage units of mentioned sizes and as per dwg. It shall consist of 19mm thk. ply top, 19mm tk. comm. ply sides, bases and 6mm tk. comm. ply backs. The edge of top will be provided with a suitable (as per Architects design). Steam Beach wooden moulding finished with natural polish at the edges of plywood. 19mm tk. comm ply to be used as shelves shall be provided at 16" intervals from the base fixed on polished wooden batten & will be finished with two coats of sythentic enamble paint and two coats of primer. Each shutters will be made of 19mm tk. comm. ply complete with 1.0mm laminate on external sides and oil paint finish on internal sides (size of shutters will not be more than 1'6"width x 5'0" height). Shutter wil have godrej make storage unit locks, 4" S.S.Handles (on each shutter), Autohinges, S.S. chains, magnet catcher, S.S.perforated jaali etc. Rate to include all other necessary hardwares/accessories. <i>(The measurement will be considered outer to outer edge of length and height of units only).</i>				
3A	1'3" TO 2'6" DEEP - FLOOR BASE TYPE STORAGE UNITS	140.00	SQ.FT.		
3B	P/F PANTRY PLATFORM STORAGE UNIT SHUTTER	18.00	SQ.FT.		
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm laminate for shutters. Providing 1/2" Tk. T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All invisible surface shall be painted with minimum 2 coats of premium 1st quality paint on the inner side of approved shade as directed.				
3C	1'6" TO 2'0" DEEP - ELECTRIC PANEL COVERING UNIT	32.00	SQ.FT.		
	Providing and fixing Electric cupboard using 18mm tk. bison panel for vertical and shelves and aluminium framing of 50x25x1.20mm thick with 6mm thick bison panel on both side for shutter with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter with approved make locks, handle, Auto hinges, ball catches. P & F of S.S Perforated Louvers - 4nos. (6"X1'0"), Glass view panel with iceline film shall be provided in each shutter etc.complete as directe. Shutter size not more than 4'-0"x2'0" each.				
3D	OLD - STORAGE UNITS	140.00	SQ.FT.		
	Removing, Shifting, Size alterations with new Ply wood members with new 1.0mm approved shade Laminate and fixing in position old Side Credenza/Low & Full height Storage Units, Pantry Platform shutters, Electrical Panel units etc. Complete as per instructions. Cleaning of old units (all surface) to be done.				
	P & F of new 6mm ply on all exposed surface with approved laminate finish Wherever required. Internal Surface to be oil painted of approved shade- 2 coats. Rate to include all new hardwares, locks, handles etc. as per instruction. Final fixed clear Length & Height measurements will be considered.				
3E	12mm GLASS SHELVES	4.00	NOS.		

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS

UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.

Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
	Providing and Fixing of New 12mm clear glass with edge polished finish of size: 4'0" x 1'6" to be fixed with F-bracket.				
4	OPENING & DOORS				
	Note: Item to include necessary hardware, 4 nos. 5" S.S finish hinges in each shutter, Door closure (80 KG) 1938 (Godrej), Godrej Rossette Handle (7945), Lock body (8447), Pin Cylinder (8449), door stopper, 3" PVC buffer at backside of door, 8" tower bolt, with full wall Jamb cover ply door frame finished with laminate as / detail & with 3" matching wood border complete. Rate to include Glass film as per design. As/specification, drawing, details & instruction of architect/EIC. <i>(The measurement will be considered doors outer to outer edge of length and height only).</i>				
4A	12mm TOUGHENED GLASS FRONT GLAZING	12.00	SQ.FT.		
	Providing and fixing fully glazed panels in front. The items shall be executed by fixing 12 mm x 12 mm x 12 mm, 1 mm th. S.S. 304 "C" shape channel fixed in the floor in consealed manner & 25 mm x 12 mm x 25 mm, 1 mm th. S.S. 304 "C" shape channel, fixed in the ceiling / fixed solid partition in consealed manner with necessary supports inside for proper strength / support.				
	The glass shall of 12 mm th. clear toughned glass with all edges machine cut, fixed with clear silicon sealant from both inside & outside & shall be provided with sufficient drying period. The entire glazing shall be erected in complete line & level. Clear visible area will be considered for measurement purpose. Item is included with white/icing film as per design provided.				
4B	ENTRANCE DOORS - 12mm TOUGHENED GLASS DOOR	2.00	NOS.		
	Size: 3'-6" x 7'-0"				
	Providing & fixing 12mm thick toughen frameless glass double door shutters with edge polish complete Double action, double doorset, 12mm toughened glass door panel on patches. Floor springs with hold open function. The item to include fixing of 12mm th. toughened glass with top patch & bottom patch fittings. The door will have patch lock, pivot, floor spring(80-120 kg), plastic profile & 18" S.S. handles (D type) fixed with the glass by making necessary cut-outs & holes.				
	The glass shall be edge polished on all sides. The entire door system shall be erected in complete line & level including Civil Work for fitting of Floor Spring. Glass film milky Frosted / iced line white film and complete with all material, labour, tools, tackles, as / the instructions of EIC				
4C	FLUSH/SEMI GLAZED DOOR WITH WOODEN FRAME	60.00	SQ.FT.		
	PM&F, 32 mm total thickness door made from 30 mm thick flush door With 10mm glass with lock rail, both sides finished with 1mm laminate fixed in wooden frame.				
4E	REFIXING OF FLUSH/SEMI-GLAZED/TELLER/ALUMINIUM DOORS.	5.00	SET		
	Removing, Shifting & Refixing of Old Doors complete with Size Alterations as per site requirements.				

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS**UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.**

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.

Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
	Providing and fixing 6mm ply with new 1mm thick approved laminate on both sides wherever required. Rate shall include NIGHT LATCH lock with handle (Godrej Make), door closure (as the case may be), door stopper, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items if reqd. and with or with out door frames. All wooden members to be polished.				
4F	FIRE RESISTANT DOOR FOR UPS	21.00	SQ.FT.		
	P & F door made from aluminium hollow pipe section frame with 6 mm Bison panel on both the side of frame complete as/drg. With dead lock, hinges, ss handle, door stopper, fire rated door closer, Painted exterior grade paint on both side as per Architect's design & instruction. Door to have 5 mm glass with film as viewing panel as per inst.. Al. sections shall be of Banco or EQ. make.				
5	HARDWARES & ACCESSORIES				
	As per approve make list. Rate to include removing old hardwares and fixing of new.				
5A	FLOOR SPRING - OZONE/DORMA MAKE	1.00	SET		
	For Toughened Glass Door				
5B	DOOR CLOSURE (80 KG OR ABOVE) 1938 (Godrej)	4.00	SET		
5C	TELESCOPIC CHANNEL (Ozone Make) - size as per requirements.	15.00	SET		
5D	DRAWER LOCK (Godrej Make)	15.00	SET		
5E	4"/6" S.S. HANDLE	20.00	SET		
5F	KEYBAORD TRAY & CPU STAND	8.00	SET		
	Key board tray & CPU Stand (black colour) - ready made. Including telescopic/double(Hafele/Ebco/solo make) approved sliders)				
6	PANELLING/BOXING WORK				
6A	WOODEN PANELLING/BOXING ON WALLS	1025.00	SQ.FT.		
	Providing and fixing panelling on wall. Framing shall consist of Heavy duty <u>Aluminium Box Sections 50mm x 50mm</u> (wall tk. 2.6mm) @ 600mm c/c Both ways horizontally and vertically on the wall.This framing would be covered by 6mm thk. comm. Ply finished in approved 1.0 mm. Thk. Laminate finished in melamine polish.				
	Rate to include additional Sections & 18mm comm. ply. boxing to be provided to fix the Indoor AC units wherever required. Cutting/Opening in plywood for fixing of electrical fixtures,switchboards, A.C. piping to be done and neatly finishes the same.				
	All open edges with Wooden moulding, lipping etc. as directed by Bank / Architect shall be provided wherever required. No RFT. Qty. shall be considered and only actual Sq.Ft. area of each measurements shall be considered				
6B	PANELLING ON WALL IN ACP FINISH (AL. FRAMES)	60	SQ.FT.		
	<u>* All ACP Sheet will be company laminated type only. ACP Sheet Lamination cover will be removed after completion of all interior work & after confirmation of Bank's Architect only. Design/Pattern/Shades will be as per Bank/Architect.</u>				

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS

UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.

Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
	Providing and fixing 4mm TH. EXTERIOR GRADE ALUMINIUM COMPOSITE PANEL finish of Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used with 0.25 mm foil with 2"x1"x1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Corning of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for External walls. Rate to include additional Sections & 18mm com. ply to be provided to fix the Indoor AC units.				
	The rate shall be included for providing proper access panel for ATM power point and shall have proper locking arrangement for plug point by providing additional framing. This item will be carried out as per manufacturer specifications. Rate also including necessary harwares/materials etc. ACP Should be considered up to two or three color combination. Complete as per Instruction of Bank/Architect. <i>(The measurement shall be made up to false ceiling only).</i>				
6C	ACP BOX WITH TRAP DOOR FOR ROLLING SHUTTER BOX	80.00	SQ.FT.		
	P & F 12 mm Waterproof ply boxing for the rolling shutters. Necessaary Aluminium framing shall be provided. The boxing shall be finished on external sides by 4mm TH. EXTERIOR GRADE ALUMINIUM COMPOSITE PANEL finish of Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used with 0.25 mm foil with 2"x1"x1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Corning of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect.				
	The item includes for providing openable shutters with necessary framework (to be fixed with structural members) for serving of rolling shutters operations. It also includes requires hardware such as hinges, elen key etc. Complete as per Instruction of Bank/Architect.				
7	FALSE CEILING				
	Contractor shall follow false ceiling work as per design provided by Bank's Architect only. No RFT. Qty. shall be considered and only actual Sq.Ft. area of each measurements shall be considered. Rate to include dismantelling of old false ceiling works.				
7A	SUSPENDED FALSE CEILING - (GYPSUM BOARD) WITH PAINT FINISH	600.00	SQ.FT.		
	Providing and fixing ½" thk. Gypsum India board false ceiling at levels as shown in the drg. from FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres.				

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS**UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.**

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.

Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
	The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffit with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres.				
	12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment.				
	The boards are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & joint paper tape. Provision for providing ceiling rope lights in double pattas will be inclusive in rate. Rate shall also be inclusive of Cut outs for A/c machiness, spot lights, light fixtures, A/C. Grills, fire and security systems cut outs, All Sections should adhere to the manufacturers guidelines. External vertical sides visible pattas will not be considered for quantity. Rate shall be inclusive of Acrylic emulsion Paint finish on Gypsum board ceiling.				
7B	SUSPENDED FALSE CEILING - (ARMSTRONG CEILINGS – FINE FISSURED MICROLOOK EDGE WITH SILHOUETTE GRID (BLACK REVEAL)	900.00	SQ.FT.		
	Providing and fixing false ceiling system manufactured by M/s. Armstrong World Industries using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42 mm web height, having 0.36 mm gauge at every 600 mm centre to centre maximum and rotary stitched cross tee of size 15 mm x 42 mm, having 0.33 mm gauge at every 600 mm. c/c. and wall angle of size 19 x 19 mm., having 0.35 mm gauge fixed to the periphery of the wall.				
	The above grid is suspended at every 600mm c/c. in both directions using 2.0 mm. thick pre-straightened GI wire laying FINE FISSURED MICROLOOK WITH SILHOUETTE GRID(BLACK REVEAL) ceiling tiles manufactured by M/s. Armstrong World Industries.				
	Size 600mmx600mmx15mm having NRC 0.55, Light reflectance of >84% (WT), thermal conductivity k = 0.052-0.057 W/m0K, Humidity Resistance of 99% , having Fire Performance CLASS O / CLASS 1 (BS 476), surface having 3 coats of white paint with Fine Fissured, back of the tile duly sanded and finished with a coat of protective paint over the formed grid complete. Complete as per Instruction of Bank/Architect				
8	PLASTIC EMULSION PAINTING WORK	200.00	SQ.FT.		
	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & finish shall be provided. (First Floor area)				
9	CUSTOMER WRITING COUNTER - 4'0"/3'-0" x 1'6" x 3'6" - 2 nos.	2.00	SET		

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS

UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.


Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
	Providing and fixing <u>New 1mm thick approved laminate</u> on external surface & oil paint on internal surface. 6mm Ply. To be used wherever required or as per instructions. New 12 mm glass for top complete with edge polish to be provided.				
10	VERTICAL BLINDS WITH SCOTCH GUARD	650.00	SQ.FT.		
	Providing & fixing Vista make or equivalent make Vertical blinds made up of powder coated channel & other imported components and rayon polyester fabric of approved shade & color. Blinds should be mounted on partition/wall using wall mounted or ceiling mounted channels as per requirement. Rate shall include necessary scotch guard treatment on both sides. The overlaps should be uniform & adequate. The rate should include with at least 12 months warranty.				
11	TEXTURED (Stucco/Metallic/Texture) OR WALLPAPER	160.00	SQ.FT.		
	Providing and applying texture paint (two colour) to walls after sand papering and cleaning the surface properly and applying the texture paint or wallpaper as per the manufacturers specifications etc all complete.				
12	THREE-SEATER SOFA	2.00	NOS.		
	(FABRIC COST B.R. Rs. 400/MTS. UBI RED COLOUR SAMPLE TO BE GOT APPROVED)				
	New Red Colour Cloth refurbishment & S.S. Legs and repairing complete with fitting & all hardwares/accessories as per instruction from Architect.				
13	3M SYNTHETIC DOOR MATS (4'-0" x 2'-0")	1.00	NOS.		
	Providing & laying in place Synthetic Door Mats (anti slippery) of sizes not less than 4' x 2' red/blue color or as per approval.				
14	MURAL PAINTINGS	4.00	NOS.		
	Providing and fixing on Site paintings as Selected by Architect .Rs 1200/- can be Considered per Painting. Final Amount shall be paid as per actual amount and actual numbers. Size : 1'6" x 2'0"				
15	PLANTERS	4.00	NOS.		
	<u>Artificial Planter</u> - Providing and fixing on Indoor artificial plants with white polished pebbles with S.S. Pot/Ceramic Pot or as Selected by Architect . Basic cost Rs 1200/-can be Considered per number. Final Amount shall be paid as per actual amount and actual numbers. Bill of purchase should be submitted for justifying basic cost.				
16	SOFT BOARD	32.00	SQ.FT.		
	Providing and fixing in position (clamp type fixing) 19 mm soft board with cloth (basic cost Rs.100=00 per mt.) with 8 mm thick commercial plywood backing and framed in 1.5" approved imported wood moulding finished in melamine polish of approved shade etc. complete.				
17	GLASS FILM	120.00	SQ.FT.		
	Providing and fixing of Glass film as per design and instructions.				
18	LUNCH TABLE - NEELKAMAL MAKE	1.00	SET		

BILL OF QUANTITIES : INTERIOR FURNISHING/RENOVATION WORKS**UBI - OLD PADRA ROAD BRANCH, VADODARA REGION, GUJARAT.**

All new wooden furnitures shall be treated with Anti Termite chemical. Contractor shall strictly follow the approve make list of each tender items as mentioned in tender.
Contractor are advised to visit the above said site before quoting the rates.

All Rates to include shifting/temporary arrangements of Furnitures & other items for smooth running of Branch irrespective of Heights/Floors.

Sr. No.	ITEM DESCRIPTION	QUANTITY	UNIT	U.RATE (Rs.)	AMOUNT (Rs.)
A	B	C	D	E	F=CXE
	Plastic table with 6 nos. of chair of neelkamal make as per approved by Architect/Bank.				
19	DISMANTELLING & SITE CLEARANCE JOB				
19A	Removing, Dismantelling of Old Existing Furnitures, woodworks, ACP, Vertical Blinds, Doors, Partitions, Counter's/ Tables, Metal Cabinete's etc. & other necessary items etc. in cordination with other's Vendors to carryout necessary Interior Works as mentioned above. Rate to include temporary arrangments, shifting/fixing of old tables. Vendor Should note that, this work shall be carried out as per instruction of Bank/Architect's as per the stage decided and to provide smooth running Banking operations including throw away the debris.	1.00	JOB		
19B	Dismatelling of old false ceilings (any type) alongwith sections & accessories and throw away the debris all complete as per the instructions of Architects/Bank. Approx area will be 1900 sq.ft.	1.00	JOB		
20	TOTAL AMOUNT OF INTERIOR & ALLIED WORKS (SUM OF 1 TO 19): IN WORDS:				
21	ADD GST @ 18% (on 20) (C.GST@9% + S.GST@9%)			18.00%	
22	FINAL GRAND TOTAL WITH GST : (20+21)				



PROJECT: UNION BANK OF INDIA - OLD PADRA ROAD BRANCH (Existing Premises)
INTERIOR LAYOUT - FIRST FLOOR, VADODARA REGION, GUJARAT.

DRG. NO. : UBII/O.P. ROAD BRANCH_INTERIOR LAYOUT - 03	DRG. DATE: 07/09/2022	NTS
PROJECT NO. : UBII/2018B-2022	CHECKED BY: AR. VIJENDRA SHAW	NTS
CLIENT DETAIL : CORPORATION BANK / BRD REGION	CHECKED BY: AR. VIJENDRA SHAW	NTS
PROJECT CONSULTANT : (SHAW ARCHITECTS)	NOTES / REMARK:	
ARCHITECTURE : INTERIORS PROJECT MANAGEMENT		
SP-28, SAMANVAY SILICON, SAVANVANI, VADODARA		
Contact No. : 9868280771		
Email : shawarchitects@gmail.com		