



Regional Office, Warangal
First Floor, NRR Congress Bhavan, Opp. Ashok Hotel, Hanmakonda 506001

TENDER NOTICE
Fire Hydrant and Sprinkler System works at Currency Chest, Hanmakonda

Union Bank of India invites applications / Bids for completion of Fire Hose related works at Currency Chest, Hanmakonda.

Title of the Cover: **“Tender for Fire Hydrant and Sprinkler System at Currency Chest, Hanmakonda”**

Name & Desig. of Official: **Chief Manager, Operations Department**
Address of the Office: **Regional Office, Warangal**
First Floor, NRR Congress Bhavan, Opp. Ashok Hotel, Hanmakonda 506001

The application forms are also available during aforesaid period on Banks website www.unionbankofindia.co.in and CPP portal www.eprocure.gov.in. Application forms containing detailed information can be collected from the above cited address of Regional Office, Hanmakonda during working hours from 10:00AM up to 5:00PM.

Firms interested in supply, installation, testing & commissioning of complete Fire Hose Reel works including required valves, fittings, pipelines etc. by adhering to government guidelines shall submit their duly filled bid in sealed covers superscribing application for **“Tender for Fire Hydrant and Sprinkler System works at Currency Chest, Hanmakonda”** on or before 22.07.2022, 05:00PM.

The applications / Bids will be opened on 22.07.2022 at 05:30PM at our Regional Office, Hanmakonda mentioned above, in the presence of applicants / their authorized representatives who wish to be present. All addendum / amendments if any, in respect of this Bid / Notice if any will be displayed on the bank's website www.unionbankofindia.co.in and www.eprocure.gov.in and no paper advertisement will be released.

Union Bank of India reserves the right for rejecting any or all applications received without assigning any reasons whatsoever.

Date: 30.06.2022
Place: Warangal

Regional Head

GENERAL INFORMATION:

- Bidders are requested to be present during tender opening. No time extension is allowed and bids submitted after due date & time will not be entertained. Bank is not liable for any postal / transit delay / loss.
- Bank reserves its right to open the bids even if no bidders / authorised representatives of the bidders are present at the stipulated time.
- All addendum / amendments in respect of this Bid / Notice, if any will be displayed on the Bank's website and no paper advertisement will be released. Intending bidders are advised to check website regularly.
- Union Bank of India reserves the right to reject any or all applications received without assigning any reasons whatsoever. No communication will be entertained. Agreement shall be executed as per Bank's guidelines upon appointment of L1 bidder.
- The tenderer is expected to have visited and studied the nature of site, scope of work, local conditions, details of construction drawings, materials and labour conditions as applicable to work.
- Tenderer must ascertain the availability of space for storage of construction materials, water supply, electricity, means of access to the work, nature of work and acquaint himself with all local conditions. A tenderer shall be deemed to have full Knowledge of all the relevant documents, samples, site, etc.
- Work under this contract shall be carried out strictly in accordance all relevant latest Indian standards, National building code (NBC), Tariff Advisory Committee (TAC), local fire approval authorities (fire service department) & any other statutory bodies.
- If there is any error in writing, no overwriting should be done, the wrong word or figure should be struck out and the correct one written above in a neat and unambiguous way. Each correction should be initialled.
- The completed application forms duly signed and stamped be placed in a sealed envelope super-scribed as **"Tender for Fire Hydrant and Sprinkler System works at Currency Chest, Hanmakonda"** to reach on or before 22.07.2022 05:00 PM. The bids will be opened on 22.07.2022 at 05:30 PM at Regional Office, Warangal.
- Address of the Office: Chief Manager, Operations Department, Union Bank of India, Regional Office Warangal, First Floor, NRR Congress Bhavan, Opp. Ashok Hotel, Hanmakonda 506001.

PRICE BID

I) Total Cost of Ownership (TCO)

S. No.	Item Description	Qty.	Unit Price (in Rs.)	Cost (in Rs.)
1.	<u>Booster Pump</u> Supply, Installation, testing & commissioning of Booster Pump 450 LPM set delivering at 35 Meter Head with 5 HP Motor Bronze Impeller, SS Shaft Handling & Transportation Charges with all fittings & accessories.	1 in nos		
2.	<u>Motor Starter</u> Supply, Installation, testing & commissioning of Booster Pump Motor Starter for 450 LPM with all fittings & accessories.	1 in nos		
3.	<u>Single Hydrant Valve</u> Supply, Installation, testing & commissioning of Stainless Steel (SS-304) Single Hydrant Landing Valve with all accessories & conforming to IS 5290-1993.	3 in nos		
4.	<u>First Aid Hose Reel Drum Set</u> Supply, Installation, testing & commissioning of First Aid Swinging Hose Reel Drum with necessary rubber pipe of 30 Meter Length with all accessories as per IS 884.	6 in nos		
5.	<u>Single Hose Box</u> Supply, Installation, testing & commissioning of Single Door Hose Box with front glass door & locking arrangement for 1 length of 15meter Canvas RRL Hose Pipe and 01 Branch Pipe duly painted in post box red colour.	3 in nos		
6.	<u>RRL Fire Fighting Hose Pipes</u> Supply, Installation, testing & commissioning of Fire Fighting RRL Hose Rubber lines woven jacketed Pipes conforming to latest IS 636, Reinforced Rubber lined (Type-B) 63 mm in diameter and 15 meter in length fitted with male & female SS couplings fitted with all accessories.	3 in nos		
7.	<u>Branch Pipe</u> Supply, Installation, testing & commissioning of SS Branch Pipe of 63 mm dia fitted with 20 mm detachable hexagonal nozzle conforming ISI Mark with all fittings.	3 in nos		
8.	<u>Butterfly Valve</u> Supply, Installation, testing & commissioning of Butterfly Valve having Cast Iron and Gun Metal working parts with Nut, Bolts, Gaskets etc & tested to 1.5 times of working pressure with fixing accessories as per IS 780 with suitable matching flanges compatible & all fittings.	As Required		
	a) 100 mm	02 in nos		
	b) 80 mm	-		
	c) 60 mm	01 in no		
9.	<u>Non-Return Valve</u> Supply, Installation, testing & commissioning of Non-Return Valve conforming to latest IS 778-1984 having Cast Iron Body & Gun Metal working parts with Galvanized Iron Nut, Bolts, Gaskets etc & tested to 1.5 times of working pressure with fixing accessories & PN 1.6 rating of valves.	01 in no		

10.	<u>Pipes</u> Supply, Installation, testing & commissioning of MS B Class Pipe conforming as per IS 1239 make for suction and delivery for Pump including bends, flanges, nuts, Bolts, welding joints. Providing and fixing with heavy anchor fastening of testing of pressure, rectifying the leakages if any, painting & all fittings & accessories.	As Required		
	a) 100 mm	-		
	b) 80 mm	60 mtrs		
	c) 50 mm	24 mtrs		
	d) 25 mm	60 mtrs		
11.	<u>2 Way Fire Brigade Tank Inlet Connection</u> Supply, installation, testing & commissioning of 2 Way Fire Brigade Inlet Connection and fabricated out of 100 mm dia. MS Pipe of suitable length with provision for 2 inlet with 63 mm dia. bearing ISI Mark with all accessories & fittings.	01 in no		
12.	<u>Sprinkler</u> Supply, installation, testing & commissioning of 1 inch Ball Valve, 1 Inch nipples, hose collars and clamp with all accessories & fittings.	06 in nos		
13.	<u>Sprinkler Heads</u> Supply, installation, testing & commissioning of Sprinkler Heads including nipples teflon tapes with all accessories & fittings.	20 in nos		
14.	<u>Fire Bucket Set</u> Supply & installation of 4 Buckets including all accessories and fittings.	1 set		
15.	<u>M.S. Angle Supports</u> Supply, Installation, testing & commissioning of MS Angle Supports to lay G.I. Pipes with anchor fasteners, nut, bolts & washers and one coat of black enamel paint with all fittings.	20 in nos		
16.	<u>Pressure Gauge</u> Supply, Installation, testing & commissioning of Pressure Gauge with siphon cock valve, GI Pipe, Elbow & all necessary fittings.	2 in nos		
17.	<u>Cable</u> Supply, Installation, testing & commissioning of PVC Armoured Cable 4 sq.mm x16 core copper conductor with all necessary accessories & fittings.	65 mtrs		
18.	Civil Work including core cutting, Excavation work, Square Block support for piping and pump foundation work charges.	Lumpsum		
18.	Total			

Grand Total = Rs._____.

Amount In Words:_____.

Applicable taxes would be paid extra.

Note:

1. Works shall be carried out by using approved brand of the material only and specifications and quality. No deviation in specifications, brand material, quality etc is permitted without the approval of the bank.
2. Rates/ Amount of items shall include cost of the material, loading, unloading, charges for tools /machineries, labour, octroi, taxes etc.
3. No extra charges shall be paid for lifting of material for any height.
4. No extra payment shall be made for carrying out the works in holiday/Sunday/night etc.
5. The contractor makes their own arrangement for safety /security of the material stacked at the site. The bank will not be responsible for any theft/mishandling of the material.
6. The Contractor shall obtain necessary labour license, insurance, permission/NOCs/approval from local authorities for supplying, installing, commissioning etc. of fire hydrant system & sprinkler system.
7. The payment of running bills/final bill will be made for the actual measurements of works carried out at the site.

(AUTHORISED SIGNATORY OF BIDDER)

Suggestion: Price-Bid may be submitted after detailed site survey to avoid any miscalculation.